

**REPAIRS TO STORM DAMAGED SCHOOL AT HARMONY HILL PRI SCHOOL
INDEPENDENT DEVELOPMENT TRUST
SIBHIDLA CONSULTING**

Item No		Quantity	Rate	Amount
	<u>BILL NO. 1</u>			
	<u>PRELIMINARIES</u>			
	<u>Preliminaries</u>			
1	Allow for preliminary works, temporary stores, scaffolding, insurances for workmen, water for works, etc to be expected as directed by the Engineer	Item		
	Carried to Summary			R
	Bill No. 1 PRELIMINARIES			

**REPAIRS TO STORM DAMAGED SCHOOL AT HARMONY HILL PRI SCHOOL
INDEPENDENT DEVELOPMENT TRUST
SIBHIDLA CONSULTING**

Item No	Quantity	Rate	Amount
<p><u>BILL NO. 2</u></p> <p><u>ALTERATIONS (PROVISIONAL)</u></p> <p><u>PREAMBLES</u></p> <p>For Preambles refer to "General Specification of Labour and Material and Methods to be used PW371"</p> <p><u>View site</u></p> <p>Before submitting his tender the tenderer shall visit the site and satisfy himself as to the nature and extent of the work to be done and the value of the materials contained in the buildings or portions of the buildings to be demolished. No claim for any variations of the contract sum in respect of the nature and extent of the work or of inferior or damaged materials will be entertained</p> <p><u>Explosives</u></p> <p>No explosives whatsoever may be used for demolition purposes unless otherwise stated</p> <p><u>General</u></p> <p>Water supply pipes and other piping in ground that may be encountered and found necessary to disconnect or cut, shall be effectually stopped off or grubbed up and removed, and any new connections that may be necessary shall be made with proper fittings to the satisfaction of the principal agent</p> <p>Unless otherwise described all materials are to become the property of the contractor and are to be removed from the site</p>			
<p>Carried Forward</p>		<p>R</p>	
<p>Bill No. 2 ALTERATIONS</p>			

**REPAIRS TO STORM DAMAGED SCHOOL AT HARMONY HILL PRI SCHOOL
INDEPENDENT DEVELOPMENT TRUST
SIBHIDLA CONSULTING**

Brought Forward			R
<u>REMOVAL OF EXISTING WORK</u>			
<u>Taking out and removing glass and mirrors</u>			
1	Clear sheet glass from steel windows in panes not exceeding 2.0 m2	m2	35
<u>INSPECT CORRUGATED IRON ROOFS</u>			
2	Inspect Corrugated roofing sheets exceeding 100m2 for cracks, leaks and damages and mark up for repairs (Repairs elsewhere measured) 295m2 x 4	m2	1 351
3	Repair leaks and make water-tight Corrugated roofing sheets and paint to match existing colour (All classroom Blocks)	m2	1 351
4	Repair leaks and make water-tight Corrugated roofing sheets and paint to match existing colour (Admin block & Kitchen)	m2	640
5	Supply rainwater goods		SUM
Carried to Summary			R
Bill No. 2 ALTERATIONS			

**REPAIRS TO STORM DAMAGED SCHOOL AT HARMONY HILL PRI SCHOOL
INDEPENDENT DEVELOPMENT TRUST
SIBHIDLA CONSULTING**

Item No		Quantity	Rate	Amount
	<p><u>BILL NO. 3</u></p> <p><u>GLAZING</u></p> <p><u>PREAMBLES</u></p> <p>For Preambles refer to "General Specification of Labour and Material and Methods to be used PW371"</p> <p><u>Float glass</u></p> <p>The term "float glass" is used for monolithic annealed glass</p> <p><u>Laminated glass</u></p> <p>Laminated glass to have polyvinyl butyral (PVB) interlayer(s)</p> <p><u>GLAZING TO STEEL WITH PUTTY</u></p> <p><u>6mm Normal strength (NS) clear laminated safety glass</u></p>			
1	Panes exceeding 0,5m ² and not exceeding 2m ²	m2	35	
	Carried to Summary			R
	Bill No. 3 GLAZING			

**REPAIRS TO STORM DAMAGED SCHOOL AT HARMONY HILL PRI SCHOOL
INDEPENDENT DEVELOPMENT TRUST
SIBHIDLA CONSULTING**

Bill No	<u>FINAL SUMMARY</u>	Page No	Amount
1	PRELIMINARIES	1	
2	ALTERATIONS	3	
3	GLAZING	4	
	Sub Total		R
	Add: Value Added Tax @ 15%		R
	Carried to Form of Tender		R