

**REPAIRS TO STORM DAMAGED SCHOOL AT LYDENBURG PRIMARY SCHOOL
INDEPENDENT DEVELOPMENT TRUST
SIBHIDLA CONSULTING**

Item No		Quantity	Rate	Amount
	<u>BILL NO. 1</u>			
	<u>PRELIMINARIES</u>			
	<u>Preliminaries</u>			
1	Allow for preliminary works, temporary stores, scaffolding, insurances for workmen, water for works, etc to be expected as directed by the Engineer	Item		
	Carried to Summary			R
	Bill No. 1 PRELIMINARIES			

**REPAIRS TO STORM DAMAGED SCHOOL AT LYDENBURG PRIMARY SCHOOL
INDEPENDENT DEVELOPMENT TRUST
SIBHIDLA CONSULTING**

Item No	Quantity	Rate	Amount
<p><u>BILL NO. 2</u></p> <p><u>ALTERATIONS (PROVISIONAL)</u></p> <p><u>PREAMBLES</u></p> <p>For Preambles refer to "General Specification of Labour and Material and Methods to be used PW371"</p> <p><u>View site</u></p> <p>Before submitting his tender the tenderer shall visit the site and satisfy himself as to the nature and extent of the work to be done and the value of the materials contained in the buildings or portions of the buildings to be demolished. No claim for any variations of the contract sum in respect of the nature and extent of the work or of inferior or damaged materials will be entertained</p> <p><u>Explosives</u></p> <p>No explosives whatsoever may be used for demolition purposes unless otherwise stated</p> <p><u>General</u></p> <p>Water supply pipes and other piping in ground that may be encountered and found necessary to disconnect or cut, shall be effectually stopped off or grubbed up and removed, and any new connections that may be necessary shall be made with proper fittings to the satisfaction of the principal agent</p> <p>Unless otherwise described all materials are to become the property of the contractor and are to be removed from the site</p>			
<p>Carried Forward</p>		<p>R</p>	
<p>Bill No. 2 ALTERATIONS</p>			

**REPAIRS TO STORM DAMAGED SCHOOL AT LYDENBURG PRIMARY SCHOOL
INDEPENDENT DEVELOPMENT TRUST
SIBHIDLA CONSULTING**

Item No		Quantity	Rate	Amount
	<u>BILL NO. 3</u>			
	<u>EXTERNAL WORKS</u>			
	<u>CIVIL WORKS</u>			
	<u>CLEARVU FENCING</u>			
	<u>Restricted Excavations:</u>			
1	Ground Beams	m3	130	
	<u>FORMWORK</u>			
	<u>Special off-form</u>			
2	To sides of ground beams	m2	42	
	<u>CONCRETE</u>			
	<u>Strength concrete 25MPa/19mm in:</u>			
3	Ground beams	m3	42	
	<u>FENCING</u>			
	<u>ClearVu fencing</u>			
4	Mesh panels 3300mm wide x 1800mm high galvanized 4mm diameter wire with aperture size at centres at 76mm x 12mm. Panel formation: Panel reinforced with 4 x 50mm deep "v" formation horizontal recessed bands, 2 x 75mm 75 degrees flanges along the sides. (Internal fixtures: anti vandal and 2 x 30 degrees flanges along top). Coating: Mesh pre galvanised then polymeric 6000 coated.	m	680	
	<u>Sundries</u>			
5	Extra over 1.8m high x 3.5m wide double leaf main vehicular access	No	1	
6	Extra over 1.8m high x 1000mm wide single pedestrian gate.	No	1	
	Carried to Summary			R
	Bill No. 3 EXTERNAL WORKS			

