

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 1</u></p> <p><u>BILL NO. 1</u></p> <p><u>PRELIMINARIES</u></p> <p><u>BUILDING AGREEMENT AND PRELIMINARIES</u></p> <p>The JBCC Principal Building Agreement (Edition 6.2 – May 2018) prepared by the Joint Building Contracts Committee shall be the applicable building agreement, amended as hereinafter described</p> <p>The JBCC Principal Building Agreement contract data form an integral part of this agreement</p> <p>The JBCC General Preliminaries (May 2018) published by the Joint Building Contracts Committee for use with the JBCC Principal Building Agreement (Edition 6.2 – May 2018) shall be deemed to be incorporated in this project specific preliminaries, amended as hereinafter described</p> <p>The contractor is deemed to have referred to the abovementioned documents for the full intent and meaning of each clause</p> <p>The contractor is deemed to have referred to the abovementioned documents for the full intent and meaning of each clause</p> <p>Where standard clauses or alternatives are not entirely applicable to this agreement such amendments, modifications, corrections or supplements as will apply are given under each relevant clause heading and such amendments, modifications, corrections or supplements shall take precedence notwithstanding anything to the contrary contained in the abovementioned documents</p>			
<p>Carried Forward</p>			R
<p>Section No. 1 Bill No. 1 PRELIMINARIES Mavusandile Solutions (PTY) LTD</p>			

Brought Forward

R

PREAMBLES FOR TRADES

The General Preambles for Trades 2017 published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in this Project Specific Preliminaries

Supplementary preambles and/or specifications are incorporated in this Project Specific Preliminaries to satisfy the requirements of this project. Such supplementary preambles and/or specifications shall take precedence over the provisions of the General Preambles

The contract sum shall take account of and include where applicable for all of the obligations, requirements and specifications given in the General Preambles and in any supplementary preambles and/or specifications

PRICING OF PRELIMINARIES

Should the **contractor** select Option A in terms of subclause 3.2.1 in the **Contract Data - Contractor to Employer** (CE) for the purpose of adjustment of these **preliminaries**, the amount entered into the amount column in these **preliminaries** is to be divided into one or more of the three categories provided namely Fixed (F), Value Related (V) and Time Related (T)

SECTION A - PRINCIPAL BUILDING AGREEMENT

Definitions (A1)

1 Clause 1.0 - Definitions and interpretation

The measuring system used for the preparation of the **bills of quantities** is the Standard System of Measuring Building Work (sixth edition, revised 1999) published by the Association of South African Quantity Surveyors [1.1]

F:..... V:..... T:.....

Item

Carried Forward

R

Section No. 1
Bill No. 1
PRELIMINARIES
Mavusandile Solutions (PTY) LTD

Brought Forward		R
<u>Objective and preparations (A2 - A14)</u>		
2	Clause 2.0 - Offer acceptance and performance obligations F:..... V:..... T:.....	Item
3	Clause 3.0 - Documents The contract drawings are as listed on the contents page of the bills of quantities Provision is made in the summary page of these bills of quantities for the inclusion of Value Added Tax (VAT) [3.5] The principal agent shall decide which portion of the priced document may be used as a specification of materials and goods or methods, if any [3.9] F:..... V:..... T:.....	Item
4	Clause 4.0 - Design responsibility F:..... V:..... T:.....	Item
5	Clause 5.0 - Employer's agents F:..... V:..... T:.....	Item
6	Clause 6.0 - Contractor's site representative F:..... V:..... T:.....	Item
Carried Forward		R
Section No. 1 Bill No. 1 PRELIMINARIES Mavusandile Solutions (PTY) LTD		

Brought Forward			R
7	<p>Clause 7.0 - Compliance with laws and regulations</p> <p>Without limiting the generality of the provisions of clause 7.0, the contractor's attention is drawn to the provisions of the Construction Regulations, 2014 issued in terms of the Occupational Health and Safety Act, 1993. It is specifically stated that the employer shall prepare a documented health and safety specification for the works and that the employer shall ensure that the contractor has made provision for the cost of health and safety measures during the execution of the works. The contractor shall price opposite this item for compliance with the act and the regulations and the reasonable provisions of the aforementioned health and safety specifications [7.1]</p> <p>F:..... V:..... T:.....</p>	Item	
8	<p>Clause 8.0 - Works risk</p> <p>F:..... V:..... T:.....</p>	Item	
9	<p>Clause 9.0 - Indemnities</p> <p>F:..... V:..... T:.....</p>	Item	
10	<p>Clause 10.0 - General insurances</p> <p>F:..... V:..... T:.....</p>	Item	
11	<p>Clause 11.0 - Special insurances</p> <p>F:..... V:..... T:.....</p>	Item	
12	<p>Clause 12.0 - Effecting insurances</p> <p>F:..... V:..... T:.....</p>	Item	
13	<p>Clause 13.0 - Assignment</p> <p>F:..... V:..... T:.....</p>	Item	
14	<p>Clause 14.0 - Security</p> <p>F:..... V:..... T:.....</p>	Item	
	<u>Execution (A15 - A23)</u>		
15	<p>Clause 15.0 - Preparation for and execution of the works</p> <p>F: V:..... T:</p>	Item	
Carried Forward			R
<p>Section No. 1 Bill No. 1 PRELIMINARIES Mavusandile Solutions (PTY) LTD</p>			

	Brought Forward		R	
16	<p>Clause 16.0 - Site and access</p> <p>The sites are as identified in the site description. Access restrictions therefore vary depending on the school. Reference as [16.1]</p> <p>Geotechnical Report is available and attached to this document [16.4]</p> <p>The school will be in operation during construction period. Reference as [16.6]</p> <p>There are no known services on site. Reference as [16.7]</p> <p>F:..... V:..... T:.....</p>			
		Item		
17	<p>Clause 17.0 - Contract instructions</p> <p>F:..... V:..... T:.....</p>			
		Item		
18	<p>Clause 18.0 - Setting out of the works</p> <p>The contractor shall notify the principal agent if any encroachments of adjoining foundations, buildings, structures, pavements, boundaries, etc. exist in order that the necessary arrangements may be made for the rectification of any such encroachments [18.1].</p> <p>F: V:.....T:.....</p>			
		Item		
19	<p>Clause 19.0 - Temporary works and plant</p> <p>Area of construction to be barricaded against intrusion by pupils. [19.1.1]</p> <p>Contractor to provide own office accommodation for meetings, etc.[19.1.2]</p> <p>Clause 19.1.1 - <i>Enclosure of the works</i></p> <p>Clause 19.1.2 - <i>Office accommodation</i></p> <p>Clause 19.2 - <i>Advertising rights and notice boards</i></p> <p>F:..... V:..... T:.....</p>			
		Item		
	Carried Forward		R	
	<p>Section No. 1</p> <p>Bill No. 1</p> <p>PRELIMINARIES</p> <p>Mavusandile Solutions (PTY) LTD</p>			

	Brought Forward		R	
20	<p>Clause 20.0 - Nominated subcontractors</p> <p>Refer to the provisions on general attendance hereinafter</p> <p>F:..... V:..... T:.....</p>	Item		
21	<p>Clause 21.0 - Selected subcontractors</p> <p>General attendance of n/s subcontractors for pricing by the contractor shall be in accordance with the n/s agreement. Notwithstanding this provision, general attendance shall be deemed to include for the contractor to provide free of charge to any n/s subcontractor such scaffolding as may reasonably be required by such n/s subcontractor for the execution of the relevant subcontract work</p> <p>F:..... V:..... T:.....</p>	Item		
22	<p>Clause 22.0 - Employer's direct contractors</p> <p>F:..... V:..... T:.....</p>	Item		
23	<p>Clause 23.0 - Contractor's domestic subcontractors</p> <p>F:..... V:..... T:.....</p>	Item		
	<u>Completion (A24 - A30)</u>			
24	<p>Clause 24.0 - Practical completion</p> <p>F:..... V:..... T:.....</p>	Item		
25	<p>Clause 25.0 - Works completion</p> <p>F:..... V:..... T:.....</p>	Item		
26	<p>Clause 26.0 - Final completion</p> <p>F:..... V:..... T:.....</p>	Item		
27	<p>Clause 27.0 - Latent defects liability period</p> <p>F:..... V:..... T:.....</p>	Item		
28	<p>Clause 28.0 - Sectional completion</p> <p>F:..... V:..... T:.....</p>	N/A		
	Carried Forward		R	
	<p>Section No. 1 Bill No. 1 PRELIMINARIES Mavusandile Solutions (PTY) LTD</p>			

**ERADICATION OF PIT LATRINES
ENZONDWANE PRIMARY SCHOOL**

	Brought Forward			R	
29	<p>Clause 29.0 - Revision of date for practical completion</p> <p>The removal and replacement of materials and/or workmanship which do not conform to specification or the contract drawings shall not constitute grounds for the extension of the construction period nor for the adjustment of the contract value (Clause 29.3)</p> <p>F:..... V:..... T:.....</p>		Item		
30	<p>Clause 30.0 - Penalty for late or non-completion</p> <p>F:..... V:..... T:.....</p> <p><u>Payment (A31 - A35)</u></p>		Item		
31	<p>Clause 31.0 - Interim payment</p> <p>The inclusion of materials and goods stored off site in the amount authorised for payment in terms of clause 31.4 shall be at the sole discretion of the principal agent and such inclusion shall only be considered upon the provision, by the contractor, of an approved guarantee issued by a registered commercial bank. Clause 31.6.5 is therefore not applicable [31.4.2, 31.6.5]</p> <p>Materials and goods stored off site shall not be included in the amount authorised for payment [31.6.5]</p> <p>F:..... V:..... T:.....</p>		Item		
Carried Forward				R	
<p>Section No. 1 Bill No. 1 PRELIMINARIES Mavusandile Solutions (PTY) LTD</p>					

	Brought Forward		R	
32	<p>Clause 32.0 - Adjustment to the contract value</p> <p>All fluctuations in costs, with the exception of fluctuations in the rate of Value Added Tax, shall be for the account of the contractor [32.13]</p> <p>Where prices are submitted by the contractor or n/s subcontractor during the progress of the works in respect of contract instructions or in regard to a claim under the terms of the contract and notwithstanding the fact that such prices may be used in an interim payment certificate, there is to be no presumption of acceptance. Should the principal agent wish to accept any such prices prior to the issue of the certificate of final completion, it shall be in writing</p> <p>The contractor shall not receive any mark-up for overheads and profit on any omission of tenant installation work or tenant installation work by others. Claims for loss or profit shall not be entertained [32.2]</p> <p>F:..... V:..... T:.....</p>	Item		
33	<p>Clause 33.0 - Recovery of expense and loss</p> <p>F:..... V:..... T:.....</p>	Item		
34	<p>Clause 34.0 - Final account and final payment</p> <p>F:..... V:..... T:.....</p>	Item		
35	<p>Clause 35.0 - Payment to other parties F:.....</p> <p>V:..... T:.....</p> <p><u>Termination (A36 - A39)</u></p>	Item		
36	<p>Clause 36.0 - Termination by employer - contractor's default</p> <p>F:..... V:..... T:.....</p>	Item		
37	<p>Clause 37.0 - Termination by employer - loss and damage</p> <p>F:..... V:..... T:.....</p>	Item		
	Carried Forward		R	
	<p>Section No. 1</p> <p>Bill No. 1</p> <p>PRELIMINARIES</p> <p>Mavusandile Solutions (PTY) LTD</p>			

	Brought Forward		R	
38	Clause 38.0 - Termination by contractor - employer's default F:..... V:..... T:.....	Item		
39	Clause 39.0 - Termination - cessation of the works F:..... V:..... T:.....	Item		
	<u>Dispute (A40)</u>			
40	Clause 40.0 - Settlement of disputes F:..... V:..... T:.....	Item		
	<u>Contract variables (A41 - A42)</u>			
41	Clause 41.0 - Post tender provisions The contractor is to complete before submission of his tender the JBCC Principal Building Agreement Contract Data CE F:..... V:..... T:.....	Item		
42	Clause 42.0 - Contractual agreement The required information of the contracting parties and the amount of the accepted contract sum shall be inserted in the agreement for signature of the agreement by the parties F:..... V:..... T:.....	Item		
	Carried Forward		R	
	Section No. 1 Bill No. 1 PRELIMINARIES Mavusandile Solutions (PTY) LTD			

Brought Forward		R	
<u>SECTION B - PRELIMINARIES</u>			
<u>Definitions and interpretation (B1)</u>			
43	Clause 1.0 - Definitions and interpretation F:..... V:..... T:.....	Item	
<u>Documents (B2)</u>			
44	Clause 2.1 - Checking of documents F:..... V:..... T:.....	Item	
45	Clause 2.2 - Provisional bills of quantities These bills of quantities are in multiple procurement format ie the "wet trades" - earthworks, concrete, formwork and reinforcement, precast concrete, masonry, waterproofing and sub-surface drainage - are provisionally fully measured and the subsequent trades are budgetary allowances and/or selected subcontract amounts F:..... V:..... T:.....	Item	
46	Clause 2.3 - Availability of construction documentation The budgetary allowances and selected subcontract amounts allocated for subsequent trades included in this agreement will be separately procured, based on multiple procurement of subcontractors during the construction period F:..... V:..... T:.....	Item	
<u>Previous work and adjoining properties (B3)</u>			
47	Clause 3.1 - Previous work - dimensional accuracy F:..... V:..... T:.....	Item	
48	Clause 3.2 - Previous work - defects F:..... V:..... T:.....	Item	
49	Clause 3.3 - Inspection of adjoining properties F:..... V:..... T:.....	Item	
Carried Forward		R	
Section No. 1 Bill No. 1 PRELIMINARIES Mavusandile Solutions (PTY) LTD			

	Brought Forward		R	
	<u>Samples, shop drawings and manufacturer's instructions (B4)</u>			
50	Clause 4.1 - Samples of materials F:..... V:..... T:.....	Item		
51	Clause 4.2 - Workmanship samples F:..... V:..... T:.....	Item		
52	Clause 4.3 - Shop drawings F:..... V:..... T:.....	Item		
53	Clause 4.4 - Compliance with manufacturer's instructions F:..... V:..... T:.....	Item		
	<u>Deposits and fees (B5)</u>			
54	Clause 5.1 - Deposits and fees F:..... V:..... T:.....	Item		
	<u>Temporary services (B6)</u>			
55	Clause 6.1 - Water F:..... V:..... T:.....	Item		
56	Clause 6.2 - Electricity F:..... V:..... T:.....	Item		
57	Clause 6.3 - Telecommunication facilities F:..... V:..... T:.....	Item		
58	Clause 6.4 - Ablution facilities F:..... V:..... T:.....	Item		
	<u>Prime cost amounts (B7)</u>			
59	Clause 7.1 - Responsibility for prime cost amounts F:..... V:..... T:.....	Item		
	<u>Special attendance on n/s subcontractors (B8)</u>			
60	Clause 8.1 - Special attendance F:..... V:..... T:.....	Item		
	Carried Forward		R	
	Section No. 1 Bill No. 1 PRELIMINARIES Mavusandile Solutions (PTY) LTD			

Brought Forward		R	
<u>General (B9)</u>			
61	Clause 9.1 - Protection of the works F:..... V:..... T:.....	Item	
62	Clause 9.2 - Protection/isolation of existing/sectionally occupied works F:..... V:..... T:.....	Item	
63	Clause 9.3 - Security of the works F:..... V:..... T:.....	Item	
64	Clause 9.4 - Notice before covering work F:..... V:..... T:.....	Item	
65	Clause 9.5 - Disturbance F:..... V:..... T:.....	Item	
66	Clause 9.6 - Environmental disturbance The employer has prepared an environmental management plan (EMP) (Refer to Annexure for a copy of the relevant plan). The contractor shall price opposite this item for compliance with all the requirements of such emp F:..... V:..... T:	N/A	
67	Clause 9.7 - Works cleaning and clearing F:..... V:..... T:.....	Item	
68	Clause 9.8 - Vermin F:..... V:..... T:.....	Item	
69	Clause 9.9 - Overhand work F:..... V:..... T:.....	Item	
Carried Forward		R	
Section No. 1 Bill No. 1 PRELIMINARIES Mavusandile Solutions (PTY) LTD			

Brought Forward	R
<p><u>Schedule of variables (B10)</u></p> <p>Information necessary for elections and completion of those clauses contained in the schedule which are necessary for tender purposes is given hereunder. Where no information is given it shall mean that no specific requirements are expected or that the clause is not relevant to this specific contract</p> <p>10.1 - Provisional bills of quantities [clause 2.2] The quantities are provisional No</p> <p>10.2 - Availability of construction documentation [clause 2.3] Construction documentation is complete Yes</p> <p>10.3 - Previous work - dimensional accuracy [clause 3.1]</p> <p>10.4 - Previous work - defects [clause 3.2]</p> <p>10.5 - Inspection of adjoining properties [clause 3.3]</p> <p>10.6 - Water [clause 7.2] Option A (by contractor) Yes Option B (by employer - free of charge) No Option C (by employer - metered) No</p> <p>10.7 - Electricity [clause 7.3] Option A (by contractor) Yes Option B (by employer - free of charge) No Option C (by employer - metered) No</p>	
<p>Carried Forward</p> <p>Section No. 1 Bill No. 1 PRELIMINARIES Mavusandile Solutions (PTY) LTD</p>	R

<p style="text-align: right;">Brought Forward</p> <p>10.8 - Telecommunications [clause 7.4]</p> <p>Telephone Yes</p> <p>Facsimile Yes</p> <p>E-mail Yes</p> <p>10.9 - Ablution facilities [clause 7.5]</p> <p>Option A (by contractor) Yes</p> <p>Option B (by employer) No</p> <p>10.10 - Protection of the works [clause 9.1]</p> <p>10.11 - Protection/isolation of existing/sectionally occupied works [clause 9.2]</p> <p>Protection/isolation is required Yes</p> <p>10.12 - Disturbance [clause 9.5]</p> <p>10.13 - Environmental disturbance [clause 9.6]</p> <p style="text-align: right;">Carried Forward</p> <p>Section No. 1 Bill No. 1 PRELIMINARIES Mavusandile Solutions (PTY) LTD</p>	<p style="text-align: center;">R</p> <hr/> <p style="text-align: center;">R</p>
--	---

Brought Forward		R
<u>SECTION C - SPECIFIC PRELIMINARIES</u>		
70	Site instructions Contract Instructions issued on site are to be recorded in triplicate in a site instruction book which is to be maintained on site by the contractor F:..... V:..... T:.....	Item
71	Warranties for material and workmanship Where warranties for materials and/or workmanship are called for, the contractor shall obtain a written warranty, addressed to the employer , from the firm supplying the materials and/or doing the work and shall deliver same to the principal agent on the final completion of the contract . The warranty shall state that workmanship, materials and installation are warranted for a specified period from the date of final completion and that any defects that may arise during the specified period shall be made good at the expense of the firm supplying the materials and/or doing the work, upon written notice to do so. The warranty will not be enforced if the work is damaged by defects in the construction of the building in which case the responsibility for replacement shall rest entirely with the contractor F:..... V:..... T:.....	Item
72	Co-operation of contractor for cost management It is specifically agreed that the contractor accepts the obligation of assisting the principal agent in implementing proper cost management. The contractor will be advised by the principal agent of all cost management procedures which will be implemented to ensure that the final building cost does not exceed the budget. The principal agent undertakes to make available to the contractor all budgetary allowances and cost assessments/reports to enable the proper procedure to be implemented and the contractor shall attend all cost plan review and cost management meetings. The contractor undertakes to extend these procedures, as necessary, to all subcontractors F:..... V:..... T:.....	Item
Carried Forward		R
Section No. 1 Bill No. 1 PRELIMINARIES Mavusandile Solutions (PTY) LTD		

	Brought Forward		R	
73	Propping of floors below The contractor is advised that propping of floors below may be required if he wishes to use any areas of completed suspended reinforced concrete slabs for vehicle access, storage of materials and goods and location of plant, scaffolding, etc. The location of these areas and any necessary propping shall be approved by the principal agent and the cost thereof shall be borne by the contractor F:..... V:..... T:.....	Item		
74	Testing of windows for watertightness Each window shall be tested for watertightness with water sprayed on using adequate pressure. If in the opinion of the principal agent , the pressure proves to be inadequate, then the pressure shall be boosted by means of compressed air or other approved means F:..... V:..... T:.....	Item		
75	Testing of flat roof waterproofing for watertightness Flat roof waterproof areas shall be flooded and kept "ponded" for at least forty (40) hours as a test to ensure the watertightness of the waterproofing and before any further construction work is carried out above the waterproofing F:..... V:..... T:.....	Item		
	<u>SECTION D: SPECIFIC PRELIMINARIES</u>			
76	Section E contains Specific Preliminary items which apply to this contract except where "N/A" (Not Applicable) appears against the item	Item		
	Carried Forward		R	
	Section No. 1 Bill No. 1 PRELIMINARIES Mavusandile Solutions (PTY) LTD			

	Brought Forward		R	
77	D1 PROPRIETARY BRANDED PRODUCTS The Contractor shall take delivery of, handle, store, use apply and/or fix all proprietary branded products in strict accordance with the manufacturers' instruction after consultation with the manufacturer's authorised representative. F:_____ V:_____ T:_____	Item		
78	D2 OVERTIME Should overtime be required to be worked for any reason whatsoever, the costs of such overtime are to be borne by the Contractor unless the Engineer/Principal Agent has specifically authorised in writing, prior to the execution thereof, that costs for such overtime are to be borne by the Employer. F:_____ V:_____ T:_____	Item		
79	D3 AS BUILT DRAWINGS The position of construction breaks and the extent of individual concrete pours are to be recorded by the Contractor on the Structural Engineer's drawings and are to be submitted to the Engineer/Principal Agent and the Structural Engineer for their records. F:_____ V:_____ T:_____	Item		
80	D4 SITE INSTRUCTIONS Site instructions issued on site are to be recorded in triplicate in a site instruction book which is to be maintained on site by the Contractor. F:_____ V:_____ T:_____	Item		
	Carried Forward		R	
	Section No. 1 Bill No. 1 PRELIMINARIES Mavusandile Solutions (PTY) LTD			

	Brought Forward		R	
81	D5 LABOUR RECORD At the end of each week, the Contractor shall provide the Engineer/Principal Agent with a written record, in schedule form, reflecting the number and description of tradesmen and labourers employed by him and all Sub-contractors on the works each day. F:_____V:_____T:_____			
	<i>Note: In the event that the contractor fails to satisfy the requirements of this specification, the Employer (Head: Public Works) may apply any of the sanctions provided in the contract. Sanctions may include the application of a financial penalty of .04% of the Contract Sum per calendar day of which the required report has not been submitted</i>	Item		
82	D6 PLANT RECORD At the end of each week the Contractor shall provide the Engineer/Principal Agent with a written record, in schedule form, reflecting the number, type and capacity of all plant, excluding hand tools, currently used on the works. F:_____V:_____T:_____			
		Item		
83	D7 NON CESSION OF MONIES The Contractor shall not cede nor assign his rights or claims to any monies due or to become due under this contract. F:_____V:_____T:_____			
		Item		
	Carried Forward		R	
	Section No. 1 Bill No. 1 PRELIMINARIES Mavusandile Solutions (PTY) LTD			

	Brought Forward		R	
84	D8 SECTIONAL COMPLETION When it is required that the contract be executed in sections or portions, the Tenderer shall allow for all costs in this regard as no claim for additional costs will be entertained. F: _____ V: _____ T: _____	Item		
85	D9 LOCAL LABOUR It is a general requirement of this contract that persons normally resident in the locality of the works (local labour) be given preference for employment on the contract. Provided, however, that should adequate and appropriate Labour not be available within the locality, other may be employed subject to satisfactory proof being provided that every reasonable endeavour has been made to employ local Labour. The Contractor shall identify the local community leaders with the purpose of negotiating with them regarding the utilization of local Labour in the construction process. In this regard, the Contractor shall furthermore give preference, wherever possible to the employment of single heads of households, women and youth and preference should be given to parents of those children that are enrolled in the school whom are not currently employed. The Contractor shall, in general, maximize the involvement of the local labour and it is required that 100% of unskilled labour should be from the local community. All standard local labour employment forms (EPWP local labour forms) together with the supporting documentation (certified ID copies, employee details, wage rates, proof of payment, period of employment, employment contracts, etc) must be submitted with the monthly payment certificates and issued to the engineer. F: _____ V: _____ T: _____	Item		
	Carried Forward		R	
	Section No. 1 Bill No. 1 PRELIMINARIES Mavusandile Solutions (PTY) LTD			

	Brought Forward		R	
86	<p>D10 IMPORT PERMITS AND DUTIES</p> <p>The responsibility for obtaining the necessary import permits shall rest with the successful Tenderer. No foreign exchange will be arranged or provided by the Administration.</p> <p>Tenderers are to allow in their tenders and pay the ordinary levy imposed on imported items in terms of item 196.10 of Part 8 of Schedule No. 1 of the Customs and Excise Act, 1964 with effect from 1 October 1989.</p> <p>F:_____V:_____T:_____</p>	Item		
87	<p>D11 CONTRACT PRICE ADJUSTMENT PROVISIONS (CPAP)</p> <p>Notwithstanding anything to the contrary contained in the GCC for Construction Works 2010 2nd Edition, this Contract shall only when the Construction Period exceeds 6 months and the Contract sum exceeds R1,000,000,00 be subject to the Contract Price Adjustment Provisions Indices Application Manual for use with P0151 indices (CPAP) (Revised 1 January 2013) as published by Statistics South Africa. Tenderers are advised that with reference to Clause 3.4.6 of the Contract Price Adjustment Provisions (CPAP) Indices Applications Manual, the Head: Public Works will not accept the submission by Tenderers of lists of additional items.</p> <p>Where this contract is a Lump Sum contract, the contract will be subject to Contract Price Adjustment Provisions (CPAP) only where the contract period equals or exceeds 6 calendar months. The applicable work group shall be WG 180 for domestic buildings or WG 181 for commercial and industrial buildings.</p> <p>F:_____V:_____T:_____</p>	Item		
	Carried Forward		R	
	<p>Section No. 1 Bill No. 1 PRELIMINARIES Mavusandile Solutions (PTY) LTD</p>			

88

Brought Forward

R

12.1 EPWP PROGRAMME

D12.1 a. Employment Targets

The Contractor needs to provide a realistic estimate on the number of jobs that the project has the potential to create throughout the project duration as the project will be implemented using labour intensive construction methods on elements where it is economical and feasible for this construction method.

No of jobs to be created is a minimum of **8 unskilled labour**

F: _____ V: _____ T: _____

It is a general requirement of this contract that persons normally resident in the locality of the works (local labour) or unemployed parents whose children attend the specific school be given preference for employment on the contract. Provided, however, that **should adequate and appropriate labour not be available within the ward**, others may be employed subject to satisfactory proof being provided that every reasonable endeavour has been made to employ local labour **(Local Sub-Contractor(s); Skilled; Semi-Skilled and Unskilled)**. The Contractor shall identify the local community leaders **(Project Steering Committee)** with the purpose of negotiating with them regarding the utilization of local labour in the construction process. In this regard, the Contractor shall furthermore give preference, wherever possible to the employment of single heads of households, women and youth as well as families declared most indigent by War on Poverty / Sukuma Sakhe program profiling process. The Contractor should aim, in general, to maximize the involvement of the local community, however workers from the communities should not exceed 20% of all persons working on the project, where local employees possess skills at level of competency that meet contractors requirements

Item

Carried Forward

R

Section No. 1

Bill No. 1

PRELIMINARIES

Mavusandile Solutions (PTY) LTD

	Brought Forward		R
89	<p>D12 EXPANDED PUBLIC WORKS PROGRAMME (EPWP)</p> <p>Tenderers are advised that this contract will be subject to certain provisions of the Expanded Public Works Program (EPWP) aimed at alleviating and reducing unemployment.</p> <p>Tenderers must allow for any costs for the following employment requirements of the EPWP.</p> <ol style="list-style-type: none"> 1. 60% of unskilled labour to be women. 2. 55% of unskilled labour to be youth aged between 18 and 35 years. 3. 2% of unskilled labour to be people living with disability. <p>100% Unskilled labour utilised must reside within the boundaries of the Municipality Ward where this contract is executed, with preference to the local community closest or at the walking distance to the contract site. Wherever possible local skilled tradesmen are to be employed on this contract with the view to maximize utilization of local resources.</p> <p>F: _____ V: _____ T: _____</p>	Item	
90	<p>D12.1 LABOUR RATE AND PAYMENT INTERVALS</p> <p>The contractor should ensure that labour rate paid to unskilled local labour is commensurate to the daily task. When determining the rate, consideration should be given to EPWP beneficiaries are mostly bread winners in their families, as the program intends alleviating poverty. There should also be consideration that the labour rate promotes creation of expanded number of jobs created and person days of work.</p> <p>Contractors should make endeavours to ensure that labourers, particularly unskilled are remunerated on fortnightly basis and prior notification be made should there be a shortfall on their wages.</p> <p>The labour rate for local unskilled shall also be determined in consideration of the location of the project, i.e. for projects implemented in urbanized municipalities will not be the same as that for rural municipalities.</p> <p>F: _____ V: _____ T: _____</p>	Item	
	Carried Forward		R
	<p>Section No. 1 Bill No. 1 PRELIMINARIES Mavusandile Solutions (PTY) LTD</p>		

91	<p style="text-align: center;">Brought Forward</p> <p>12.2 LABOUR INTENSIVE CONSTRUCTION METHOD D12.2 a Labour Intensive Construction (LIC) Method</p> <p>On site there must a person(s) having competency in managing and implementing LIC methods *Foreman @ NQF Level 4 the Unit Standard on Implementing LIC methods on site*Site Agent/Managers @ NQF level 5 the Unit Standard on Manage Labour-Intensive Skills Programme both must be CETA accredited. F: _____ V: _____ T: _____</p> <p>D12.2 b Labour Intensive Construction Method Those parts of the contract to be constructed using Labour Intensive methods will be marked in the BoQ with letter LI (indicating Labour Intensive) against every item so designated. Such works will only be constructed using method so indicated. Reference to be made to Guidelines for the implementation of Labour Intensive Infrastructure projects under EPWP. "Scope of Work in Respect of Work Relating to the Expanded Public Works Programme (EPWP)"</p> <p>Labour-intensive component Due to the nature of the work involved, this type of project lends itself to be feasible as a labour-Intensive project i.e. the construction activities will indeed require skilled/unskilled labour.</p> <p>The aim of the projects is to provide some form of economic benefit whilst generating and increasing the acquired skills shortage to improve sustainability in the local area. The following are potential focus areas where employment creation can be optimized per project:</p> <p>(i) Trenching works not exceeding depth of 1.5m, including trenching for Foundation, Electrical, Water, Mechanical & Civil Services Works including backfilling where ground conditions permit</p> <p>(ii) Building Works; All masonry works (which include concrete mixing on site; brickwork; block work ; plastering; screed works; jointing; etc.); Painting, Plumbing, Ironmongery; roof cladding; glazing; tiling; carpentry; flooring; waterproofing; etc.</p> <p>(iii) Sewers works including Construction of manholes, laying of Sewer pipes, bedding, backfilling and compaction.</p> <p style="text-align: center;">Carried Forward</p> <p>Section No. 1 Bill No. 1 PRELIMINARIES Mavusandile Solutions (PTY) LTD</p>	<p style="text-align: center;">R</p> <hr/> <p style="text-align: center;">R</p>
----	--	---

Brought Forward		R	
	Item		
92	<p>(iv) Water Reticulation works including excavation, bedding, laying of pipes and compaction</p> <p>(v) Site Clearance Works</p> <p>(vi) Electrical Reticulation works.</p> <p>(vii) Stormwater water drainage using in-situ concrete</p> <p>(viii) Landscaping and Grassing of Sports Field</p> <p>(ix) Cleaning and Fencing Works</p> <p>The above identified activities are deemed suitable to be constructed using the LIC methods; to build, upgrade and maintain the social and economic of the underdeveloped area, promoting community participation, development of skills and creating more work opportunities.</p> <p>The above identified activities should be marked in the Bill of Quantities with the letter (LI). Contractor to price the above items in the Bill of Quantities bearing in mind that they are regarded as the main sources of job creation, whether sub contracted or undertaken by the main contractor</p> <p>The use of plant to provide such works, other than plant specifically provided for in the scope of work, is a variation to the contract. The items marked with the letter LI are not necessarily an exhaustive list of all the activities which must be done by hand.</p> <p>Payment for items which are designated to be constructed labour-intensively (either in this schedule or in the Scope of Works) will not be made unless they are constructed using labour-intensive methods. Any unauthorised use of plant to carry out work which was to be done labour-intensively will not be condoned and any works so constructed will not be certified for payment.</p> <p>F:_____V:_____T:_____</p>		
	Item		
Carried Forward		R	
Section No. 1 Bill No. 1 PRELIMINARIES Mavusandile Solutions (PTY) LTD			

	Brought Forward		R
93	<p>D12.3 RECORD KEEPING</p> <p>12.3.1 Every employer must keep in the project site office the following minutes of site progress minutes; contractors' monthly site progress reports; accurately recorded attendance register; proof of payment as means to verify authenticity of data in the EPWP Beneficiary form submitted with payment certificates. Copies of submitted EPWP beneficiary data forms should also be kept in the site office.</p> <p>12.3.2 The employer must keep this record for a period of at least three (3) years after the completion of the project in his/her office as the project site office would have been relocated.</p> <p>This should be safely kept for job creation data verifications and periodical audits on projects conducted by National and Provincial Department of Public Works after one (1) or two (2) quarters of submitting captured EPWP Data to the National EPWP coordinating Department.</p> <p>F:_____ V:_____ T:_____</p>	Item	
94	<p>D12.4 EPWP MONTHLY REPORTING DOCUMENTS</p> <p>At the end of each month the contractor must submit:</p> <p>EPWP monthly data collection form Worker monthly payment upload Worker monthly acknowledgement of receipt of payment Worker monthly Payment register Worker monthly training form Monthly attendance Register Worker Monthly pay slips Unskilled labour certified ID copies (once off) Beneficiary ID-size photos Proof of UIF Proof of COIDA</p> <p>F:_____ V:_____ T:_____</p>	Item	
	Carried Forward		R
	<p>Section No. 1 Bill No. 1 PRELIMINARIES Mavusandile Solutions (PTY) LTD</p>		

	Brought Forward		R	
95	D12.5 EPWP PROMOTION 12.5.1. EPWP signage board EPWP Program at the project level shall always be promoted through the provision of projects signage board that embraces EPWP logo at the bottom, correct measurement for this sign board will be provided by the project leader during the site handing over meeting. F:_____V:_____T:	Item		
96	D13 EPWP contract for labour It is compulsory that shortly after the contractor and or sub contractor has appointed local labour, the employment contract should be signed by both parties, prior to commencement with works on site. The employment contract forms part of the Ministerial Determination or from the regional EPWP officials F.....V.....T.....	Item		
97	D14 EPWP Scope of Work For This Project Contractors are to price the items on the Bill of Quantities highlighted below, bearing in mind that they are regarded as main sources of job creation, whether sub contracted or undertaken by the main contractor. Elements of the scope of work where the application of Labour Intensive Construction methods are indicated with the letters (LI) are as follows; Excavating trenches for foundations and any other civil works with the depth not more than 1.5 m All masonry works which include concrete mixing on site; brickwork; plastering; screed works; jointing; etc. Painting, Plumbing, Ironmongery; roof cladding; glazing; tiling; carpentry; flooring; waterproofing; etc. External works such as landscaping; cleaning; paving; fencing; tarmac; etc. F.....V.....T.....	Item		
	Carried Forward		R	
	Section No. 1 Bill No. 1 PRELIMINARIES Mavusandile Solutions (PTY) LTD			

	Brought Forward		R	
98	12.5.2 Branding of labour apparel Contractor & Sub-contractors' labourers shall be provided with EPWP branded Personal Protective Equipment (PPE), reflector vest with EPWP acronym at the back as an ideal and cost effective means of promoting program on site. The contractor is advised to price for both items 12.5.1 and 12.5.2 F: _____ V: _____ T: _____	Item		
99	D12 COMMUNITY LIAISON OFFICER (CLO) UTILISATION OF A COMMUNITY LIAISON OFFICER The Contractor shall allow for and pay any and all costs necessary for the engagement of the services of a Community Liaison Officer (CLO) for the full duration of this contract Provide the sum of R19 500.00 for the employment of a Community Liaison Officer to be employed by the Main Contractor and be paid an allowance of R6 500.00 a month for the duration (3 months) A CLO will be identified by the local structures (Project Steering Committee) of the ward areas and appointed following fair and transparent interviewing process, to be conducted in the presence of local structures and the contractor representative, in order to assist the Contractor in the procurement of any local labour, etc. required for this project. The Contractor is to liaise with the CLO and afford him any assistance needed in ensuring sound working relations with the local community.	Item		19 500,00
100	Key responsibilities of the CLO are envisaged to include and not necessarily be limited to: 1. Assisting local leadership in conducting skills and resources audit which facilitates sourcing labour from within the ward or targeted areas for employment, as required by Contractor 2. Assisting in sourcing labour-only domestic Sub-contractors and the procurement of materials from local resources, as required by the Contractor. 3. Assisting the Contractor by identifying areas of			
	Carried Forward		R	
	Section No. 1 Bill No. 1 PRELIMINARIES Mavusandile Solutions (PTY) LTD			

Brought Forward	R	
<p>potential conflict and or threats to the project or to stakeholders in the project and recommend appropriate action to the Contractor.</p> <p>4. Assisting Contractor and stakeholders in the project in the resolution of any conflicts which may arise.</p> <p>5. Establishing and ensuring that sufficient and open communication channels between the Contractor and the work force are maintained.</p> <p>6. Establish and ensuring that efficient and open communication channels between the Contractor and the community are maintained.</p> <p>7. Identifying and reporting to the Contractor regarding issues where communication between stakeholder is necessary, recommend courses of action and facilitate such communications.</p> <p>8. Assisting the Contractor and the workforce in the establishment of grievance procedures and necessary recommendations to the Contractor regarding the grievances and solution thereto</p> <p>9. Attending to site meetings and project implementation meetings as required by the Contractor and preparing periodic reports as may be required by the Contractor, from time to time.</p> <p>10. Attending to such other duties which are consistent with the functions of a CLO, as may be required by the Contractor, from time to time.</p> <p>Tenderers are to price twice the rate of unskilled local labour rate for the Community Liason Officer (CLO) against this item for any and all costs arising out of compliance with the foregoing and in the event of a Tenderer failing to price against this item or making inadequate financial provision against this item for compliance as aforesaid, then no claim for costs or additional cost incurred will be entertained by the Head: F: _____ V: _____ T: _____</p>	Item	
Carried Forward	R	
<p>Section No. 1 Bill No. 1 PRELIMINARIES Mavusandile Solutions (PTY) LTD</p>		

Brought Forward

SUMMARY OF CATEGORIES - MAIN WORKS
ONLY EXCLUDING SHE AMOUNT

Category: Fixed R

Category: Value R

Category: Time R

R

Carried to Final Summary

R

Section No. 1

Bill No. 1

PRELIMINARIES

Mavusandile Solutions (PTY) LTD

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 2</u>			
	<u>BILL NO. 1</u>			
	<u>ALTERATIONS</u>			
	<u>Preambles</u>			
	TheTenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2008 Edition)			
	<u>SUPPLEMENTARY PREAMBLES</u>			
	<u>View site</u>			
	Before submitting his tender the contractor shall visit the site and satisfy himself as to the nature and extent of the work to be done and the value of the materials contained in the buildings or portions of the buildings to be demolished. No claim for any variations of the contract sum in respect of the nature and extent of the work or of inferior or damaged materials will be entertained			
	<u>General</u>			
	The contractor shall carry out the whole of the works with as little mess and noise as possible and with a minimum of disturbance to adjoining premises and their tenants. He shall provide proper protection and provide, erect and remove when directed, any temporary tarpaulins that may be necessary during the progress of the works, all to the satisfaction of the principal agent			
	Water supply pipes and other piping that may be encountered and found necessary to disconnect or cut, shall be effectually stopped off or grubbed up and removed, and any new connections that may be necessary shall be made with proper fittings, to the satisfaction of the principal agent			
	Carried Forward		R	
	Section No. 2 Bill No. 1 ALTERATIONS Mavusandile Solutions (PTY) LTD			

<p style="text-align: center;">Brought Forward</p> <p>Doors, fanlights, fittings, frames, linings, etc which are to be re-used shall be thoroughly overhauled before re-fixing including taking off, easing and rehangings, cramping up, re-wedging as required and making good cramps, dowels, etc, and easing, oiling, adjusting and repairing ironmongery as necessary, replacing any glass damaged in removal or subsequently and stopping up all nail and screw holes with tinted plastic wood to match timber, unless otherwise described. Re-painting or re-varnishing is given separately.</p> <p>Prices for taking out of doors, windows, etc shall include for removal of all beads, architraves, ironmongery, etc</p> <p>Prices for taking out and removing doors and frames shall include for removing door stops, cabin hooks, etc and making good floor and wall finishes to match existing</p> <p>With regard to building up of openings in existing walls, cement screeds and pavings, granolithic, tops of walls, etc, shall be levelled and prepared for raising of brickwork</p> <p>Making good of finishes shall include making good of the brick and concrete surfaces onto which the new finishes are applied, where necessary</p> <p>The contractor will be required to take all dimensions affecting the existing buildings on the site and he will be held solely responsible for the accuracy of all such dimensions where used in the manufacture of new items (doors, windows, fittings, etc)</p> <p>Asbestos work may only be performed subject to prior approval of the Provincial Director, Occupational Health and Safety, department of Labour in writing</p>	<p style="text-align: center;">R</p>
<p style="text-align: center;">Carried Forward</p> <p>Section No. 2 Bill No. 1 ALTERATIONS Mavusandile Solutions (PTY) LTD</p>	<p style="text-align: center;">R</p>

Brought Forward		R	
<p>Proof of such notification must be applied to the Client prior to work proceeding. All employees must be informed and receive training on aspects such as the contents and scope of the Asbestos Regulations as published in Government Gazette 23108 dated 10 February 2002, the potential risks of exposure to asbestos, precautionary measures employees have to take and all other requirements deemed necessary to provide a safe and healthy environment for all employees as specified by the Asbestos Regulations as indicated above.</p> <p>Disposal shall be done under strict accordance of the act.</p> <p>Contractors will be held responsible for all damage, however caused, to ceilings, finishes, etc. inside rooms where the existing roof coverings have been removed and he must make good all damage at his own expense to the approval of the employer. Contractors are to Cover and maintain existing roofs in a perfectly watertight condition during alterations by means of heavy tarpaulins properly secured and maintained in position to the approval of the Employer and make good all work damaged or distributed after completion</p> <p><u>REMOVAL OF EXISTING WORK</u></p> <p><u>Taking out and removing doors, windows, etc. from brickwork to remain</u></p>			
1	Timber single door and frame size 900 x 2100mm high, complete	No	24
2	Steel window size 1500 x 600mm high including burglar bars, complete	No	8
<u>Taking down, removing and disposing of roofs, floors, panelling, ceilings, partitions, etc</u>			
3	Timber roof trusses (measured flat on plan)	m2	151
4	Carefully take out asbestos roof covering including sisalation, timber purlins, etc. (By specialist approved Sub-Contractor)	m2	151
Carried Forward		R	
<p>Section No. 2 Bill No. 1 ALTERATIONS Mavusandile Solutions (PTY) LTD</p>			

**ERADICATION OF PIT LATRINES
ENZONDWANE PRIMARY SCHOOL**

Brought Forward			R
<u>Carefully take out and remove gutters and downpipes etc.</u>			
5	Existing box gutter	m	49
6	Existing asbestos downpipes including outlet, bends & shoe	m	22
7	Existing fascia boards	m	43
8	Existing barge boards	m	35
<u>Hacking up/off and removing granolithic, screeds, plaster, etc from concrete or brickwork and preparing surfaces for new screeds, plaster, tile finishes, etc</u>			
9	Plaster from walls	m2	210
10	30mm Screed from floors	m2	128
<u>Taking out and removing piping, sanitary fittings, etc including disconnecting piping from fittings and making good floor and wall finishes (making good tiling and paintwork elsewhere)</u>			
11	Vitreous china WC and cistern	No	24
12	Vitreous china wash hand basin	No	12
13	Vitreous china urinal	No	2
<u>PREPARATORY WORK TO EXISTING SURFACES</u>			
14	Hacking surface of existing floors to create key to receive new floor finish	m2	128
<u>PREPARATORY WORK TO EXISTING SURFACES</u>			
15	Sanding and cleaning existing steel gates, complete	m2	11
16	Pressure clean down external facebrick walls and seal with an approved sealer, complete	m2	190
Carried Forward			R
Section No. 2 Bill No. 1 ALTERATIONS Mavusandile Solutions (PTY) LTD			

Brought Forward			R
<u>SERVICING OF WINDOWS / DOORS / GATES</u>			
<u>Overhaul, adjust and service to ensure proper operation existing steel windows in brickwork and replacing any broken glass panes with 6mm clear float glass</u>			
17	Existing window size 1500 x 600mm high	No	8
<u>SERVICING OF STEEL GATES</u>			
18	(C.G1& X.G1) Single gate size 900 x 2100mm high (LI)	No	6
<u>REMOVAL OF EXISTING WORK</u>			
<u>Desludging</u>			
19	Clean out pit latrine by desludging including removal of all debris and waste including solid waste as per Health and Safety requirements and make good on completion including disposing of all debris and waste at an authorised municipal waste disposal facility. Contractor to price per seat		Item
20	Issue of Certificate of Waste Disposal.		Item
<u>TEMPORARY BARRIERS, SCREENS, ETC</u>			
<u>Temporary barriers, screens, etc including removal</u>			
21	Temporary shade cloth screen 2000mm high of 70% green shade cloth including posts, fixing, etc.	m	60
<u>TEMPORARY GATE</u>			
<u>Temporary Double swing gate for construction vehicles.</u>			
22	Double swing gate 5000mm wide x 2400mm high with 50 x 38 x 5 mm handle and catch with 15mm diameter hole for padlock. The bottom lock have 2mm washer welded to bar to serve as a stopper and 38 x 50 5mm to be guided with 20mm diameter holes	No	1
Carried to Final Summary			R
Section No. 2			
Bill No. 1			
ALTERATIONS			
Mavusandile Solutions (PTY) LTD			

Item No	Quantity	Rate	Amount
<u>SECTION NO. 3</u>			
<u>BILL NO 1</u>			
<u>ROOF COVERINGS ETC</u>			
<u>Preambles</u>			
TheTenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2008 Edition)			
<u>WORK GROUP 124</u>			
<u>PROFIED METAL SHEETING AND ACCESSORIES</u>			
<u>0.58mm Zinc alum Z250 broad flute IBR finish Top chromadek pre - coated roof sheeting (charcoal) laid at 18 degrees pitch on 75 x 50mm purlins at +/- 1200mm centres max. on Sisalation RSA 420 underlay under purlins on straining tape on timber trusses laid as per manufacturers specification. 0.8mm Flashings pre-painted to match roof sheeting and fixed in strict accordance with manufacturer's instructions.</u>			
1	Roof coverings with pitches not exceeding 50 degrees	m2	63
2	0.5mm thick ridge capping	m	8
3	Moulded narrow or broad rib polyethelene filler blocks	m	21
<u>ROOF AND WALL INSULATION</u>			
Carried Forward			R
Section No. 3 Bill No. 1 ROOF COVERINGS Mavusandile Solutions (PTY) LTD			

Brought Forward			R
	<u>"Sisalation 420" heavy industrial grade aluminium foil based insulation</u>		
4	Reflective foil insulation or equal approved 402 Heavy industrial grade reinforced aluminium foil insulation double sided, heavy grammage reflective foil laminate incorporating eight layers of aluminium foil, reinforcing scrim, Kraft paper and polyethylene, tested for conformance with SABS 1381: Part IV- 1985, with a Class 1 fire rating in accordance with SABS 0177: part III - 1981 and BS 476 part 5, 6 and 7, secured to each truss/rafter with 38mm x 3,2mm x 1100mm hardboard counter batten strips positioned flush with the bottom edge of the material thus leaving 150mm overlap exposed at the top for the next layer and 150mm overlap thereafter on each 1250mm width roll. All to be fixed in accordance with manufactures specification.	m2	63
	<u>Sundries</u>		
5	"Sondor" Eave Polycloser	m	21
Carried Forward to Summary of Section No. 3			R
Section No. 3			
Bill No. 1			
ROOF COVERINGS			
Mavusandile Solutions (PTY) LTD			

Item No	Quantity	Rate	Amount
<u>SECTION NO. 3</u>			
<u>BILL NO 2</u>			
<u>CARPENTRY AND JOINERY</u>			
<u>Preambles</u>			
TheTenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2008 Edition)			
<u>WORK GROUP 126</u>			
<u>ROOFS, ETC</u>			
<u>Plate nailed timber roof truss construction</u>			
<p>Timber roof truss prices are to include for the design, supply,wind category as per SANS 10160 and erection of the trusses into position complete including bolts, connectors, connections, etc.The dimensions of the trusses given in the following descriptions are nominal and the actual measurements for the design and manufacture of the trusses must be taken on site to match existing.The truss spans given are measured horizontally between the outer faces of the wall plates. Permanent bracing and runners have not been measured in accordance with the Standard System of Measuring Builder's Work and are measured as an item, the price of which is to include for the design, supply and fixing of necessary permanent bracing and runners.</p>			
Carried Forward			R
Section No. 3 Bill No. 2 CARPENTRY AND JOINERY Mavusandile Solutions (PTY) LTD			

Brought Forward				R
<u>Monoplaner Prefabricated Connector Plate Roof</u> <u>Trussesat 1600mm maximum centres with a pitch of</u> <u>25 Degrees and suitable for EVERITE Nutec Bigsix</u> <u>corrugated roof sheeting or other equal approved</u> <u>with 50 x 76mm purlins(elsewhere measured) at</u> <u>1050mm centres and Gypsum plasterboard ceiling</u> <u>(Gypsum plasterboard ceiling elsewhere measured)</u> <u>with brandering at 450mm centres</u>				
1	Design, supply and install prefabricated timber roof truss system complete, designed in accordance with the Standard Building Regulations and the Engineer's requirements, measured on the flat plan area of the roof inclusive of overhangs	m2	63	
<u>Sawn softwood</u>				
2	38 x 114mm Wall plates	m	16	
3	38 x 114mm Bracing	m	8	
4	50 x 76mm Purlins, bolted	m	14	
<u>Sundries</u>				
5	Hurrican clips	No	16	
<u>TR1 and TR2 Certificates</u>				
6	Allow for TR1 and TR2 certification of all trusses		Item	
<u>EAVES, VERGES, ETC</u>				
<u>"Everite" medium density plain nutec-cement</u>				
7	80 x 200mm Barge boards including H-profile jointing strips	m	14	
<u>"Everite Nutec" medium density fibre cement fascia boards (Product No. 041-202).</u>				
8	15 x 225mm Fascias including Pvc H-profile jointing strips	m	16	
<u>DOORS, ETC</u>				
Carried Forward				R
Section No. 3 Bill No. 2 CARPENTRY AND JOINERY Mavusandile Solutions (PTY) LTD				

Brought Forward			R
<u>External Commercial Grade Entrance Door:</u>			
9	Meranti standard hardwood swing door with Z bracings behind and two hardwood edge strips. 2032 x 813 x 44mm Meranti single swing entrance door complete with approved Z bracings behind sanded down or imperfections & finished with 1 coat of pink wood primer , completed with 2 coats of eggshell gloss enamel paint. All to architect's later spec. Door Hung on 2.5 mm galvanised mild steel standard pressed Single rebate frame fit for 1 brick wall	No	4
<u>Internal Medium Duty Standard Door:</u>			
10	Horizontal Slatted 8 Panel Semi Solid Meranti hardwood panel door with in 8 sections to both sides of door and two hardwood edge strips: 2032 x 813 x 44mm. Door complete with a 100mm under cut . Door to be hung on Hardwood Meranti Single rebate door Jambs . Door complete with pink primer & 2 coats eggshell gloss enamel paint.	No	8
<u>FRAMED FRAMES, ETC</u>			
<u>Timber frames</u>			
11	108 x 44mm rebated timber door frames for 813x 2032mm door with 5 x 5 mm inner rebate and 14 x 14mm chamfered outward exposed edge for stiles and top frame securely retro fixed to walls	No	8
Carried Forward to Summary of Section No. 3			R
Section No. 3			
Bill No. 2			
CARPENTRY AND JOINERY			
Mavusandile Solutions (PTY) LTD			

**ERADICATION OF PIT LATRINES
ENZONDWANE PRIMARY SCHOOL**

Item No			Quantity	Rate	Amount
	<u>SECTION NO. 3</u>				
	<u>BILL NO 3</u>				
	<u>IRONMONGERY</u>				
	<u>Preambles</u>				
	TheTenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2008 Edition)				
	<u>WORK GROUP 132</u>				
	<u>HINGES, BOLTS, ETC</u>				
	<u>Approved</u>				
1	1.5 pairs 108mm brass butt hinges	Pairs	10,0		
	<u>LOCKS</u>				
	<u>"Union"</u>				
2	Union 2261-76SS 4 lever upright lock with and including Union AL684 - 05AS bishop lever furniture	No	4		
3	Facility indicator bolt, code 37651RH	No	8		
	<u>SUNDRIES</u>				
	<u>"Supreme Hygiene" or similar approved</u>				
4	TR3 - 3 Tier Toilet roll holder Lockable	No	10		
5	Liquid Soap Dispenser	No	2		
6	She Bin 12L	No	10		
	<u>Door Closer</u>				
7	Union 87001SS door stop	No	12		
	Carried Forward				R
	Section No. 3 Bill No. 3 IRONMONGERY Mavusandile Solutions (PTY) LTD				

Brought Forward			R
8	<p><u>Door signs or numbers to be of an approved grey ultra high impact acrylic plastic construction plugged to wall or screwed to door with 15mm countersunk raised head chromium plated screws at each corner or hung from ceilings with two chromium plated chains</u></p> <p>200 x 70 x 2.5mm Sign with 40mm high letters to centre of main door leaf 1850mm above ffl (Allow for 10 Letters)</p>	No	1
Carried Forward to Summary of Section No. 3			R
Section No. 3			
Bill No. 3			
IRONMONGERY			
Mavusandile Solutions (PTY) LTD			

Item No	Quantity	Rate	Amount
<u>SECTION NO. 3</u>			
<u>BILL NO 4</u>			
<u>METALWORK</u>			
<u>Preambles</u>			
TheTenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2008 Edition)			
<u>WORK GROUP 136</u>			
<u>HOT DIP GALVANISED STEEL WINDOWS</u>			
<u>The following units refer to the Architects diagrams, details and specifications bound into the back of these bills of quantities and must be adhered to in all respects and all prices are to include all glass, ironmongery,, fixing,sealing etc</u>			
1	Standard window size 533 x 654mm	No 8	
2	Standard window size1500 x 600mm	No 4	
Carried Forward to Summary of Section No. 3			R
Section No. 3			
Bill No. 4			
METALWORK			
Mavusandile Solutions (PTY) LTD			

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 3</u>			
	<u>BILL NO 5</u>			
	<u>PLASTERING</u>			
	<u>Preambles</u>			
	TheTenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2008 Edition)			
	<u>WORK GROUP 142</u>			
	<u>SCREEDS</u>			
	<u>Screeds on concrete</u>			
1	30mm Thick on floors and landings	m2	48	
	<u>INTERNAL PLASTER</u>			
	<u>Cement plaster on brickwork</u>			
2	On superstructure internal walls	m2	90	
	Carried Forward to Summary of Section No. 3			R
	Section No. 3			
	Bill No. 5			
	PLASTERING			
	Mavusandile Solutions (PTY) LTD			

Item No		Quantity	Rate	Amount
<u>SECTION NO. 3</u>				
<u>BILL NO 6</u>				
<u>PLUMBING AND DRAINAGE</u>				
<u>(PROVISIONAL)</u>				
<u>Preambles</u>				
TheTenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2008 Edition)				
<u>WORK GROUP 146</u>				
<u>RAINWATER DISPOSAL</u>				
<u>Seamless Aluminium Gutters and Downpipes</u>				
1	125 x 75 x 0,6mm aluminium ogee gutter with baked enamel finish fixed with concealed brackets.	m	21	
2	Long-arm –Swan-neck100 Bend combination	No	2	
3	Extra for stopped end	No	4	
4	Extra for outlet for 75mm pipe	No	2	
5	100 x 75 x 0,6mm Fluted aluminium downpipes with white baked enamel finish.	m	6	
6	Extra for bend	No	2	
7	Extra for shoe	No	2	
8	Spreader for 75mm pipe	No	2	
<u>WORK GROUP 148</u>				
Carried Forward				R
Section No. 3				
Bill No. 6				
PLUMBING AND DRAINAGE(PROVISIONAL)				
Mavusandile Solutions (PTY) LTD				

**ERADICATION OF PIT LATRINES
ENZONDWANE PRIMARY SCHOOL**

Brought Forward			R
<u>SANITARY FITTINGS</u>			
9	Atlas VIP 200 floor mounted plastic seat overall size 482 x 650 x 505mm standard toilet pedestal with baby seat & lid. Colour; Granite and including Atlas VIP 200 inlet funnel or similar approved	No	10
10	382AP Christy wash hand basin including brackets,etc.	No	4
<u>TAPS, VALVES, ETC</u>			
<u>Brass</u>			
11	COBRA WATERTECH (Code. 232-10-15) fullway isolating ball valves with plastic coated plated steel lever handle	No	4
12	No.KM2 15mm pillar tap with blue inlay.	No	4
13	20mm Stopcock.	No	4
<u>SANITARY PLUMBING</u>			
<u>PVC pipes</u>			
14	50mm Waste pipe.	m	30
15	200mm diameter, 2.5mm HDPVC vent pipe attached to RoofWhirllys4Africa Toilet / Sewer Ventilator to Fit on 110mm Pipe A Energy Saving, Silent Operation, Anti Dust Tower Fan (Black).	m	28
<u>Extra for:</u>			
16	50mm Fittings	No	15
17	110mm Fittings	No	15
18	50mm Rubber S trap with side outlet.	No	6
<u>WATER SUPPLY</u>			
Carried Forward			R
Section No. 3 Bill No. 6 PLUMBING AND DRAINAGE(PROVISIONAL) Mavusandile Solutions (PTY) LTD			

ERADICATION OF PIT LATRINES ENZONDWANE PRIMARY SCHOOL

Brought Forward			R
	<u>Polycop pipe</u>		
19	15mm pipe from tank to sink	m	30
20	22mm Polycop pipe to walls,etc	m	20
	<u>Extra over Class 2 copper pipes for brass compression fittings</u>		
21	15mm Fittings	No	20
22	22mm Fittings	No	12
	<u>The following in JoJo 5500 litre capacity tanks (Stromy sky ME 5513 in colour)</u>		
23	JOJO / ROTO TANKS or similar approved 5000 Litre Low Profile light duty cylindrical polyurethane water storage tank complete with lid, 15mm brass bibtap with handle suitable for locking and 4 No. galvanised stay wires 2.5m each long connected to tank, with and including 4 No. eye bolts cast into concrete.	No	1
Carried Forward to Summary of Section No. 3			R
Section No. 3			
Bill No. 6			
PLUMBING AND DRAINAGE(PROVISIONAL)			
Mavusandile Solutions (PTY) LTD			

Item No		Quantity	Rate	Amount
<u>SECTION NO. 3</u>				
<u>BILL NO 7</u>				
<u>GLAZING</u>				
<u>Preambles</u>				
TheTenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2008 Edition)				
<u>WORK GROUP 150</u>				
<u>6.38mm thick laminated safety glass panels. All edges of the glazing panels to be treated and fully sealed with Betaseal to avoid delamination and penetrating stains.</u>				
1	6.38mm Arctic Snow safety laminated glass	m2	4	
<u>MIRRORS</u>				
2	Polished Stainless steel mirror (1 mm thick) Size: 400x300x1.0mm vertically above each basin 670mm above floor - screw fixed with countersunk stainless steel Philips screws on four corners. Rear surface of the mirror and plastic wall-plugs securely epoxy-glued to wall	No	4	
Carried Forward to Summary of Section No. 3				R
Section No. 3				
Bill No. 7				
GLAZING				
Mavusandile Solutions (PTY) LTD				

Item No		Quantity	Rate	Amount
	<u>SECTION NO. 3</u>			
	<u>BILL NO 8</u>			
	<u>PAINTWORK</u>			
	Preambles			
	TheTenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2008 Edition)			
	<u>WORK GROUP 152</u>			
	<u>PAINTWORK, ETC TO NEW WORK ON</u>			
	<u>FLOATED PLASTER SURFACES WITH</u>			
	<u>One coat Dulux trade alkali resistant plaster primer, apply one Dulux Trade universal undercoat and two coats full strength,dulux pearlglo solvent based enamel (or similar approved)</u>			
1	Internal walls	m2	90	
	<u>FIBRE-CEMENT SURFACES WITH</u>			
	<u>Two coats pure acrylic paint on</u>			
2	Fascias and barge boards	m2	8	
	<u>METAL SURFACES WITH</u>			
	<u>Clean with galvanised iron cleaner,apply one coat galvanised iron primer,one coat undercoat and two coats enamel</u>			
3	Door frame	m2	3	
4	Security gates	m2	4	
	Carried Forward		R	
	Section No. 3 Bill No. 8 PAINTWORK Mavusandile Solutions (PTY) LTD			

**ERADICATION OF PIT LATRINES
ENZONDWANE PRIMARY SCHOOL**

Brought Forward			R
<u>Global Roofing 0,60mm "Klip-Lok 700" concealed fix galvanized roof sheeting with "Chromadek" finish on one side including KL700 clips fixed to timber purlins according to manufacturer's instructions</u>			
<u>WOOD SURFACES WITH</u>			
<u>Two coats oil wood primer on</u>			
5	Backs of frames, linings, etc not exceeding 300mm wide	m	41
<u>One coat Dulux Supergrip primer wood primer,one coat Dulux Trade Universal Undercoat,two coats Dulux Pearl glo Waterbased Enamel paint on</u>			
6	Door frames	m2	2
7	Doors	m2	36
<u>Prepare and apply two coats carbolineum on:</u>			
8	Roof timbers.	m2	36
Carried Forward to Summary of Section No. 3			R
Section No. 3			
Bill No. 8			
PAINTWORK			
Mavusandile Solutions (PTY) LTD			

ERADICATION OF PIT LATRINES
ENZONDWANE PRIMARY SCHOOL

Bill No	SECTION SUMMARY - GIRLS - 10G, 4WHB	Page No	Amount
1	ROOF COVERINGS	36	
2	CARPENTRY AND JOINERY	39	
3	IRONMONGERY	41	
4	METALWORK	42	
5	PLASTERING	43	
6	PLUMBING AND DRAINAGE(PROVISIONAL)	46	
7	GLAZING	47	
8	PAINTWORK	49	
Carried to Final Summary			R
Section No. 3			
Mavusandile Solutions (PTY) LTD			

Item No	Quantity	Rate	Amount
<u>SECTION NO.4</u>			
<u>BILL NO 1</u>			
<u>ROOF COVERINGS ETC</u>			
<u>Preambles</u>			
TheTenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2008 Edition)			
<u>WORK GROUP 124</u>			
<u>PROFILED METAL SHEETING AND ACCESSORIES</u>			
<u>0.58mm Zinc alum Z250 broad flute IBR finish Top chromadek pre - coated roof sheeting (charcoal) laid at 18 degrees pitch on 75 x 50mm purlins at +/- 1200mm centres max. on Sisalation RSA 420 underlay under purlins on straining tape on timber trusses laid as per manufacturers specification. 0,8mm Flashings pre-painted to match roof sheeting and fixed in strict accordance with manufacturer's instructions.</u>			
1	Roof covering with pitch not exceeding 18 degrees.	m2	32
2	Ridge capping 500mm girth, screwed through sheet to purlins	m	6
3	0,8mm Thick cover flashing piece	m	6
4	Hole through metal roof sheeting for and flashing around 110mm pipe with Fibreglass and sealing with resin	No	2
5	Moulded narrow or broad rib polyethelene filler blocks	m	16
Carried Forward			R
Section No. 4 Bill No. 1 ROOF COVERINGS Mavusandile Solutions (PTY) LTD			

Brought Forward			R
<p><u>Extra Over for Translucent polycarbonate roof sheeting Make Allowance for 15 % of all roof sheets to be 1.2mm Broad Flute Global Roofing Solutions (GRS) Clear Heavy Duty Polycarbonate Roof Sheeting including all necessary fittings & fixtures to Manufactures Specification.</u></p>			
6	0.58 mm translucent polycarbonate roof sheeting to match roof profile, complete with proprietary fixings	m2	4
<p><u>ROOF AND WALL INSULATION</u></p> <p><u>"Sisalation 420" Reflective foil insulation or equal approved 402 Heavy industrial grade reinforced aluminium foil insulation double sided, heavy grammage reflective foil laminate incorporating eight layers of aluminium foil, reinforcing scrim, Kraft paper and polyethylene, tested for conformance with SABS 1381: Part IV- 1985, with a Class 1 fire rating in accordance with SABS 0177: part III - 1981 and BS 476 part 5, 6 and 7, secured to each truss/rafter with 38mm x 3,2mm x 1100mm hardboard counter batten strips positioned flush with the bottom edge of the material thus leaving 150mm overlap exposed at the top for the next layer and 150mm overlap thereafter on each 1250mm width roll. All to be fixed in accordance with manufactures specification.</u></p>			
7	Insulation laid taut over purlins and fixed concurrent with roof covering, including taped laps and nylon straining wires as per manufacturers specification	m2	32
<p><u>Sundries</u></p>			
8	"Sondor" Eave Polycloser	m	16
<p>Carried Forward to Summary of Section No. 4</p> <p>Section No. 4 Bill No. 1 ROOF COVERINGS Mavusandile Solutions (PTY) LTD</p>			R

Item No	Quantity	Rate	Amount
<u>SECTION NO.4</u>			
<u>BILL NO 2</u>			
<u>CARPENTRY AND JOINERY</u>			
<u>Preambles</u>			
TheTenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2008 Edition)			
<u>WORK GROUP 126</u>			
<u>ROOFS, ETC</u>			
<u>Plate nailed timber roof truss construction</u>			
<u>Sawn softwood:</u>			
1	Design, supply and install prefabricated timber roof truss system complete, designed in accordance with the Standard Building Regulations and the Engineer's requirements, measured on the flat plan area of the roof inclusive of overhangs	m2	32
2	38 x 114mm Wall plate.	m	11
3	50 x 76mm Purlins.	m	22
4	76 x 50mm Cross bracing	m	11
5	Hurricane clips	No	54
Carried Forward			R
Section No. 4 Bill No. 2 CARPENTRY AND JOINERY Mavusandile Solutions (PTY) LTD			

Brought Forward			R
6	Prior to the erection of all the roof trusses the consulting engineer shall certify that he has received such working drawings and construction detail designs from the professional engineer employed by the contractor and that he has considered same and given permission to proceed with the fabrication of the trusses (TR1 certificate issued by Contractor's Engineer) and then before the roof covering commences the completed structure shall be inspected and certified as stable by the professional engineer employed by the contractor to ensure that the manufacture of the trusses and erection details have been complied with to his satisfaction (TR2 certificate issued by Contractor's Engineer)	Item	
<u>EAVES, VERGES, ETC</u>			
<u>"Aluminium" or equal approved</u>			
7	12 x 225mm Fascia board (product no (041-202) or equal approved. Aluminium H-Profile fascia joiners (product no 685-1950. Drill and for fix with Hot dipped galvanised screws and washers.	m	11
8	0,7 x 240mm seamless aluminium anthracite grey powder coated Barge boards. drill and fix with Hot dipped galvanise screws and washers. 76 x 50mm trimmer batten fixed underside of purlin ends for barge board fixing.	m	7
<u>DOORS ETC</u>			
<u>MERANTI edging on all sides: Meranti standard hardwood swing door with Z bracings behind and two hardwood edge strips. 2032 x 813 x 44mm</u> <u>Meranti single swing entrance door complete with approved Z bracings</u>			
9	Door size 813 x 2032mm high External door	No	2
Carried Forward			R
Section No. 4 Bill No. 2 CARPENTRY AND JOINERY Mavusandile Solutions (PTY) LTD			

ERADICATION OF PIT LATRINES ENZONDWANE PRIMARY SCHOOL

Brought Forward			R
	<u>Horizontal Slatted 8 Panel Semi Solid Meranti hardwood panel door with in 8 sections to both sides of door and two hardwood edge strips: 2032 x 813 x 44mm. Door complete with a 100mm under cut . Door to be hung on Hardwood Meranti Single rebate door Jambs</u>		
10	Door size 813 x 2032mm high Internal door	No	4
	<u>Horizontal Slatted 5 Panel Solid Meranti hardwood panel door with in 5 sections to both sides of door and two hardwood edge strips: 1200mm x 813 x 44mm. Door to be hung on Hardwood Meranti Single rebate door Jambs</u>		
11	Door size 813 x 1200mm high internal Grade R door	No	
	<u>FRAMED FRAMES, ETC</u>		
	<u>Meranti Frames bolted to wall with expanding masonry bolts - four per style including quadrant beads on both sides:</u>		
12	50 x 108mm rebated meranti frame	No	54
Carried Forward to Summary of Section No. 4			R
Section No. 4 Bill No. 2 CARPENTRY AND JOINERY Mavusandile Solutions (PTY) LTD			

Item No	Quantity	Rate	Amount
<u>SECTION NO.4</u>			
<u>BILL NO 3</u>			
<u>IRONMONGERY</u>			
<u>Preambles</u>			
TheTenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2008 Edition)			
<u>WORK GROUP 132</u>			
<u>HINGES, BOLTS, ETC</u>			
<u>"UNION" or equal approved</u>			
1	SS2BB BUTT HINGE EN 1935GRD13 (Stainless Steel) - Code JH-BB-STD-22-SS-01	No 6	
2	Bolt Indicator Satin Chrome Union CZ80941SCR	No 4	
<u>LOCKS</u>			
<u>"ASSA ABLOY" or equal approved</u>			
3	"Gower" CZ6822461CH Gower 4 Lever Lockset Solid cast zinc handle and zinc backplate	No 2	
<u>SUNDRIES</u>			
<u>"Union" or equal approved</u>			
4	Floor Door Stop Satin (Stainless Steel) Code 87001SS.	No 6	
<u>BATHROOM FITTINGS</u>			
<u>"Supreme Hygiene" or similar approved</u>			
5	TR3 - 3 Tier Toilet roll holder Lockable	No 4	
Carried Forward			R
Section No. 4 Bill No. 3 IRONMONGERY Mavusandile Solutions (PTY) LTD			

ERADICATION OF PIT LATRINES
ENZONDWANE PRIMARY SCHOOL

Brought Forward			R	
6	Waste disposal bin 27L mounted on the wall	No	1	
7	Liquid Soap Dispenser	No	4	
8	She Bin 12L	No	2	
Carried Forward to Summary of Section No. 4			R	
Section No. 4				
Bill No. 3				
IRONMONGERY				
Mavusandile Solutions (PTY) LTD				

[illegible]

[illegible]

Item No	Quantity	Rate	Amount
<u>SECTION NO.4</u>			
<u>BILL NO 6</u>			
<u>PLASTERING</u>			
<u>Preambles</u>			
TheTenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2008 Edition)			
<u>WORK GROUP 142</u>			
<u>GRANOLITHIC</u>			
<u>Untinted granolithic on concrete:</u>			
1	30mm Thick on floors. m2	32	
<u>SCREEDS</u>			
<u>Screeds on concrete</u>			
2	30mm Thick on floors and landings m2	32	
<u>POLYURETHANE FLOOR FINISH</u>			
<u>Prepare existing concrete surface and apply approved 4 mm heavy-duty polyurethane cement floor finish, complete with primer, body coat, seal coat and 100 mm high integral coved skirting, all in accordance with the manufacturer's recommendations:</u>			
3	On floors m2	32	
<u>INTERNAL PLASTER</u>			
<u>Cement plaster on brickwork</u>			
4	On superstructure internal walls m2	60	
Carried Forward to Summary of Section No. 4			R
Section No. 4			
Bill No. 6			
PLASTERING			
Mavusandile Solutions (PTY) LTD			

Item No		Quantity	Rate	Amount
<u>SECTION NO.4</u>				
<u>BILL NO 7</u>				
<u>PLUMBING AND DRAINAGE</u>				
<u>(PROVISIONAL)</u>				
<u>Preambles</u>				
TheTenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2008 Edition)				
<u>WORK GROUP 146</u>				
<u>RAINWATER DISPOSAL</u>				
<u>0.6mm Seamless aluminium gutters and downpipes</u>				
1	125 x 75mm high gutters fixed to falls in continuous lengths at not exceeding 1000mm centres with and including approved gutter brackets.	m	11	
2	100 x 75mm rainwater downpipe	m	6	
3	Long-arm –Swan-neck100 Bend combination	No	2	
4	Extra over rainwater pipe for shoe	No	2	
5	Extra eaves gutter for stopped end.	No	2	
6	Extra over rainwater downpipe for bend	No	4	
<u>TRAPS ETC</u>				
<u>Rubber traps, etc.:</u>				
7	40 x 40mm 'Flexitrap' butyl rubber deep seal 'P' or 'S' trap jointed to waste outlet fitting and to PVC pipe including coupling clamps, etc.	No	2	
<u>TAPS, VALVES, ETC</u>				
Carried Forward				R
Section No. 4				
Bill No. 7				
PLUMBING AND DRAINAGE(PROVISIONAL)				
Mavusandile Solutions (PTY) LTD				

**ERADICATION OF PIT LATRINES
ENZONDWANE PRIMARY SCHOOL**

Brought Forward			R
<u>Cobra Watertech or Similar approved</u>			
8	(Code. 232-10-15) fullway isolating ball valves with plastic coated plated steel lever handle	No	2
<u>Brass</u>			
9	Cobra Water tech 15mm chrome plated elbow action raised nose pillar tap with blue indicator for cold water (Code: 503-21B), manufactured in accordance with SANS 226:2004 Type 2 (BS 5412).	No	2
10	No.KM2 15mm pillar tap with blue inlay.	No	2
11	20mm Stopcock.	No	4
<u>SANITARY FITTINGS</u>			
<u>Atlas Plastics or similar approved</u>			
12	Wall Hung Urinal : PRODUCT CODE 705426/705427 DESCRIPTION .Vaal Sanitaryware vitreous china wall hung "Lavatera" urinal with top inlet (code 705426) or back inlet (code 705427). Overall size 600 x 385 x 380 mm. Top inlet fittings (code 7054Z1) and back inlet fittings (code 7054Z2) include a 38 mm c.p. domical grating, a spreader (with a 20 mm diameter thread), and two brackets. No Traps Req	No	
13	Atlas VIP 200 floor mounted plastic seat overall size 482 x 650 x 505mm standard toilet pedestal with baby seat & lid. Colour; Granite	No	4
14	Atlas "Bambi Long Drop" (code 613AP) with footpiece complete with seat and lid screwed in precast slab including inlet funnel (code 224AP) riveted to shaft	No	
15	VAAL WHB MIDI WEAVER RECTANGULAR 1TH COUNTER BASIN 450X350 White Ceramic Wash Hand Basin including matching ceramic pedastal to manufacturers recommendations code: 706601. Including All Flexi Connectors, Plumbing finished and fixtures	No	4
Carried Forward			R
Section No. 4 Bill No. 7 PLUMBING AND DRAINAGE(PROVISIONAL) Mavusandile Solutions (PTY) LTD			

**ERADICATION OF PIT LATRINES
ENZONDWANE PRIMARY SCHOOL**

Brought Forward			R
<u>Extra for:</u>			
<u>SANITARY PLUMBING</u>			
<u>PVC waste or vent pipes and fittings:</u>			
16	50mm Waste pipe.	m	40
17	50mm Bend.	No	6
18	50mm Access bend.	No	4
19	50mm Rubber S trap with side outlet.	No	5
<u>Polycop pipe</u>			
20	15mm pipe from tank to sink	m	54
<u>WATER SUPPLY</u>			
<u>Class 2 Copper Pipes</u>			
21	20mm Pipe and fixing to walls, floors, in roofs, soffit of concrete slab, in chases (including chases), in concrete, etc.	m	65
22	15mm Pipe and fixing to walls, floors, in roofs, soffit of concrete slab, in chases (including chases), in concrete, etc.	m	23
<u>Extra over class 2 copper pipes for brass compression fittings</u>			
23	20mm Fittings	No	17
24	15mm Fittings	No	9
Carried Forward			R
Section No. 4 Bill No. 7 PLUMBING AND DRAINAGE(PROVISIONAL) Mavusandile Solutions (PTY) LTD			

Brought Forward		R	
<u>The following in JOJO / ROTO 5000 litre capacity tanks</u>			
25	JOJO / ROTO TANKS or similar approved 5000 Litre Low Profile light duty cylindrical polyurethane water storage tank complete with lid, 15mm brass bibtap with handle suitable for locking and 4 No. galvanised stay wires 2.5m each long connected to tank, with and including 4 No. eye bolts cast into concrete.	No	1
Carried Forward to Summary of Section No. 4		R	
Section No. 4			
Bill No. 7			
PLUMBING AND DRAINAGE(PROVISIONAL)			
Mavusandile Solutions (PTY) LTD			

Item No	Quantity	Rate	Amount
<u>SECTION NO.4</u>			
<u>BILL NO 8</u>			
<u>GLAZING TO STEEL WITH PUTTY</u>			
<u>Preambles</u>			
TheTenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2008 Edition)			
<u>WORK GROUP 150</u>			
<u>6.38 mm laminated "Arctic Snow" obscure safety glass secured into galvanised steel windows with compatible UV-resistant structural glazing sealant complete, all in accordance with SANS 10400</u>			
1	Panes exceeding 0,1m2 and not exceeding 0,5m2.	m2	1
2	Panes exceeding 0,5m2 and not exceeding 1,0m2.	m2	1
3	Issue glazing certificate of compliance	Item	
<u>MIRRORS</u>			
<u>6mm Silvered float glass copper backed mirrors with polished edges holed for and fixed with chromium plated dome capped mirror screws with rubber buffers to plugs in brickwork or concrete</u>			
4	400x300mm mirror	No	2
Carried Forward to Summary of Section No. 4			R
Section No. 4			
Bill No. 8			
GLAZING			
Mavusandile Solutions (PTY) LTD			

Item No	Quantity	Rate	Amount
<u>SECTION NO.4</u>			
<u>BILL NO 9</u>			
<u>PAINTWORK</u>			
<u>Preambles</u>			
TheTenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2008 Edition)			
<u>PAINTWORK, ETC TO NEW WORK ON</u>			
<u>WORK GROUP 152</u>			
<u>FLOATED PLASTER SURFACES WITH</u>			
<u>One coat Dulux trade alkali resistant plaster primer, apply one Dulux Trade universal undercoat and two coats full strength,dulux pearlglo solvent based enamel (or similar approved)</u>			
1	Internal walls	m2 60	
<u>FIBRE-CEMENT SURFACES</u>			
<u>Prepare and brush surface to remove loose contaminants and apply one coat professional gypsum & plaster primer PP700, and two coats "Plascon Wall 'n All (WAA)" or equal approved emulsion paint</u>			
2	Fascias and barge boards	m2 2	
<u>METAL SURFACES WITH</u>			
Carried Forward			R
Section No. 4 Bill No. 9 PAINTWORK Mavusandile Solutions (PTY) LTD			

**ERADICATION OF PIT LATRINES
ENZONDWANE PRIMARY SCHOOL**

Brought Forward			R
<u>Prepare surfaces and remove all loose material, check for dents in frame and fill with body filler as required. Wash down with galv clean. Touch up factory applied primer and apply one undercoat, followed by two coats Eggshell enamel paint</u>			
3	On window frames	m2	2
4	On door frames	m2	10
<u>Two coats oil wood primer on</u>			
5	Backs of frames, linings, etc not exceeding 300mm wide	m	15
<u>WOOD SURFACES</u>			
<u>Prepare, sand down and brush surface to remove all loose contaminants, and apply one coat 1 coat of pink wood primer , completed with 2 coats of eggshell gloss enamel paint. All to architect's later spec.</u>			
6	On doors	m2	10
<u>Prepare and brush surface to remove all loose contaminants and apply Four coats "ABE Provonite" or equal approved carbolineum anti-corrosive coal tar paint on All Trusses</u>			
7	On exposed timbers.	m2	28
Carried Forward to Summary of Section No. 4			R
Section No. 4			
Bill No. 9			
PAINTWORK			
Mavusandile Solutions (PTY) LTD			

ERADICATION OF PIT LATRINES ENZONDWANE PRIMARY SCHOOL

Bill No	SECTION SUMMARY - STAFF - 4S, 4WHB	Page No	Amount
1	ROOF COVERINGS	52	
2	CARPENTRY AND JOINERY	55	
3	IRONMONGERY	57	
4	METALWORK	58	
5	TILING	59	
6	PLASTERING	60	
7	PLUMBING AND DRAINAGE(PROVISIONAL)	64	
8	GLAZING	65	
9	PAINTWORK	67	
Carried to Final Summary			R
Section No. 4 Mavusandile Solutions (PTY) LTD			

Item No	Quantity	Rate	Amount
<u>SECTION NO.5</u>			
<u>BILL NO. 1</u>			
<u>ROOF COVERINGS ETC</u>			
<u>Preambles</u>			
TheTenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2008 Edition)			
<u>WORK GROUP 124(METAL ROOF)</u>			
<u>PROFILED METAL SHEETING AND ACCESSORIES</u>			
<u>0.58mm Zinc alum Z250 broad flute IBR finish Top chromadek pre - coated roof sheeting (charcoal) laid at 18 degrees pitch on 75 x 50mm purlins at +/- 1200mm centres max. on Sisalation RSA 420 underlay under purlins on straining tape on timber trusses laid as per manufacturers specification. 0,8mm Flashings pre-painted to match roof sheeting and fixed in strict accordance with manufacturer's instructions.</u>			
1	Roof covering with pitch not exceeding 15 degrees.	m2	56
2	Ridge capping 500mm girth, screwed through sheet to purlins	m	9
<u>Sundries</u>			
3	Polyethylene ridge closures	m	17
4	Broad flute ridge closures	m	17
5	Hurricane clips	No	112
<u>ROOF AND WALL INSULATION</u>			
Carried Forward			R
Section No. 5 Bill No. 1 Roof Coverings Mavusandile Solutions (PTY) LTD			

Brought Forward					R
	<p><u>Reflective foil insulation or equal approved 402 Heavy industrial grade reinforced aluminium foil insulation double sided, heavy grammage reflective foil laminate incorporating eight layers of aluminium foil, reinforcing scrim, Kraft paper and polyethylene, tested for conformance with SABS 1381: Part IV- 1985, with a Class 1 fire rating in accordance with SABS 0177: part III - 1981 and BS 476 part 5, 6 and 7, secured to each truss/rafter with 38mm x 3,2mm x 1100mm hardboard counter batten strips positioned flush with the bottom edge of the material thus leaving 150mm overlap exposed at the top for the next layer and 150mm overlap thereafter on each 1250mm width roll. All to be fixed in accordance with manufactures specification.</u></p>				
6	<p>Insulation laid taut over purlins (at approximately 1100mm centres) and fixed concurrent with roof covering including galvanised steel straining wires at 500mm centres</p>	m2	56		
<p>Carried Forward to Summary of Section No. 5</p>					R
<p>Section No. 5 Bill No. 1 Roof Coverings Mavusandile Solutions (PTY) LTD</p>					

Item No	Quantity	Rate	Amount
<u>SECTION NO.5</u>			
<u>BILL NO.2</u>			
<u>CARPENTRY AND JOINERY</u>			
<u>Preambles</u>			
TheTenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2008 Edition)			
<u>SUPPLEMENTARY PREAMBLES</u>			
<u>Joinery:</u>			
Descriptions of frames shall be deemed to include frames, transomes, mullions, rails, etc			
Descriptions of hardwood joinery shall be deemed to include pelleting of bolt holes			
<u>Fixing</u>			
Items described as "nailed" shall be deemed to be fixed with hardened steel nails or shot pins to brickwork or concrete			
<u>Decorative laminate finish:</u>			
Laminate finish shall be glued under pressure. Edge strips shall be butt jointed at junctions with adjacent similar finish			
<u>Plate nailed timber roof truss construction</u>			
The following is applicable in respect of roof trusses:			
Carried Forward			R
Section No. 5 Bill No. 2 Carpentry & Joinery Mavusandile Solutions (PTY) LTD			

Brought Forward					R
<p>Trusses are at maximum 1200mm centres and purlins are at maximum 1200mm centres The references given in the descriptions are to the respective types of trusses detailed on the architect's drawings numbered 021MAV008 annexed to these bills of quantities/accompanying these bills of quantities for tender purposes. The dimensions in the descriptions of the trusses are nominal and actual measurements are to be obtained from the architect and/or the site before design or fabrication commences</p> <p><u>WORK GROUP 126</u></p> <p><u>ROOFS ETC</u></p> <p><u>Plate nailed timber roof truss construction</u></p> <p>The following is applicable in respect of roof trusses:</p> <p>Trusses are at maximum 900mm centres The dimensions in the descriptions of the trusses are nominal and actual measurements are to be obtained from the architect and/or the site before design or fabrication commences</p> <p><u>Monoplaner Prefabricated Connector Plate Roof Trussesat 1600mm maximum centres with a pitch of 25 Degrees and suitable for EVERITE Nutec Bigsix corrugated roof sheeting or other equal approved with 50 x 76mm purlins(elsewhere measured) at 1050mm centres and Gypsum plasterboard ceiling (Gypsum plasterboard ceiling elsewhere measured) with brandering at 450mm centres</u></p>					
1	Design, supply and install prefabricated timber roof truss system complete, designed in accordance with the Standard Building Regulations and the Engineer's requirements, measured on the flat plan area of the roof inclusive of overhangs	m2	56		
<u>Sawn softwood SA Pine grade 4</u>					
2	38 x 114mm Wall plates bedded level on and including cement mortar	m	14		
3	50 x 75mm Purlins	m	69		
Carried Forward					R
<p>Section No. 5 Bill No. 2 Carpentry & Joinery Mavusandile Solutions (PTY) LTD</p>					

	Brought Forward			R
4	38 x 114mm Bracing	m	15	
	<u>TR1 and TR2 Certificates</u>			
5	Allow for TR1 and TR2 certification of all trusses		Item	
	<u>EAVES, VERGES, ETC</u>			
	<u>"Everite" medium density plain nutec-cement</u>			
	<u>'Everite Nutec' fibre cement socket less barge boards (Product no. 721-800):</u>			
6	80 x 200mm Barge boards including H-profile jointing strips	m	14	
	<u>"Everite Nutec" medium density fibre cement fascia boards (Product No. 041-202).</u>			
7	15 x 225mm Fascias including Pvc H-profile jointing strips	m	16	
	<u>FRAMED DOORS, ETC</u>			
	<u>Wrought meranti doors as hung to steel frames</u>			
	<u>Meranti standard hardwood swing door with Z bracings behind and two hardwood edge strips. 2032 x 813 x 44mm Meranti single swing entrance door complete with approved Z bracings behind sanded down or imperfections & finished with 1 coat of pink wood primer , completed with 2 coats of eggshell gloss enamel paint. All to architect's later spec</u>			
8	44mm Door, size 813 x 2032mm high	No	10	
	<u>Horizontal Slatted 8 Panel Semi-Solid panel door with in 8 sections to both sides of door and two hardwood edge strips: 2032 x 813 x 44mm. Door complete with a 100mm under cut . Door to be hung on Hardwood Meranti Single rebate door Jambs .Door complete with pink primer & 2 coats eggshell gloss enamel paint.</u>			
9	44mm Door, size 813 x 2032mm high	No	2	
	Carried Forward to Summary of Section No. 5			R
	Section No. 5			
	Bill No. 2			
	Carpentry & Joinery			
	Mavusandile Solutions (PTY) LTD			

Item No	Quantity	Rate	Amount
<u>SECTION NO.5</u>			
<u>BILL NO.3</u>			
<u>IRONMONGERY</u>			
<u>Preambles</u>			
TheTenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2008 Edition)			
<u>SUPPLEMENTARY PREAMBLES</u>			
<u>Finishes to ironmongery</u>			
Where applicable finishes to ironmongery are indicated by suffixes in accordance with the following list: BS Satin bronze lacquered CH Chromium plated SC Satin chromium plated SE Silver enamelled GE Grey enamelled AS Anodised silver AB Anodised bronze AG Anodised gold ABL Anodised black PB Polished brass PL Polished and lacquered PT Epoxy coated SD Sanded			
<u>"Union"</u>			
<u>WORK GROUP 132</u>			
<u>LOCKS</u>			
1	ASSA ABLOY UNION CZ6822461CH Gower 4 Lever Lockset Solid cast zinc handle and zinc backplate, SABS Approved	No	2
2	Union SS2BB BUTT HINGE EN 1935GRD13 (Stainless Steel) - Code JH-BB-STD-22-SS-01.	No	12
3	Bolt Indicator Satin Chrome Union CZ80941SCR	No	10
Carried Forward			R
Section No. 5 Bill No. 3 Ironmongery Mavusandile Solutions (PTY) LTD			

**ERADICATION OF PIT LATRINES
ENZONDWANE PRIMARY SCHOOL**

Brought Forward			R
<u>DOOR CLOSERS</u>			
4	Union Floor Door Stop Satin (Stainless Steel) Code 87001SS.	No	12
<u>BATHROOM FITTINGS</u>			
<u>"Supreme Hygiene" or similar approved</u>			
5	TR3 - 3 Tier Toilet roll holder Lockable	No	10
6	Waste disposal bin 27L mounted on the wall	No	2
7	Liquid Soap Dispenser	No	2
8	She Bin 12L	No	
<u>"Chairman Industries cc" grab rails</u>			
9	Code KB26, 300 x 300 x 300 x 50mm Stainless steel dog leg side grab rail fixed in position.	No	
10	Code KB18, 800 long x 50mm Projecting stainless steel straight grab rail fixed in position	No	
<u>SIGNAGE</u>			
<u>Union Male, Female , Male + Female / Paraplegic Engraved Pictogram signage:</u>			
11	Stainless steelGrade 201 Stainless Steel Signage Plate,600mm X 1252mm X 1.2mm . Supplied with 4 mounting screws - Pozi head 14.6x3.87mm Radius end plates to eliminate sharp cormers after mounting plate Counter-sunk screw holes - screws will have a nice flush finish with the signage	No	1
Carried Forward to Summary of Section No. 5			R
Section No. 5			
Bill No. 3			
Ironmongery			
Mavusandile Solutions (PTY) LTD			

Item No	Quantity	Rate	Amount
<u>SECTION NO.5</u>			
<u>BILL NO. 4</u>			
<u>METALWORK</u>			
<u>Preambles</u>			
TheTenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2008 Edition)			
<u>SUPPLEMENTARY PREAMBLES</u>			
<u>Descriptions</u>			
Descriptions of bolts shall be deemed to include nuts and washers			
Descriptions of expansion anchors and bolts and chemical anchors and bolts shall be deemed to include nuts, washers and mortices in brickwork or concrete			
Metalwork described as"holed for bolt(s)" shall be deemed to exclude the bolts unless otherwise described			
<u>WORK GROUP 136</u>			
<u>GALVANISED STEEL WINDOWS, DOORS, ETC</u>			
All windows shall be fitted with solid brass handles, screws, stays and hinge pins.			
<u>Standard commercial windows with heavy duty solid brass ironmongery with opening sections fitted with standard burglar bars.</u>			
1	E1 533 x 654mm high. (W1)	No	4
2	E2 1500 x 600mm High (W2)	No	3
Carried Forward to Summary of Section No. 5			R
Section No. 5			
Bill No. 4			
Metalwork			
Mavusandile Solutions (PTY) LTD			

Item No		Quantity	Rate	Amount
	<u>SECTION NO.5</u>			
	<u>BILL NO.5</u>			
	<u>PLASTERING</u>			
	Preambles TheTenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2008 Edition)			
	<u>WORK GROUP 142</u>			
	<u>SCREEDS</u>			
	<u>Untinted granolithic on concrete</u>			
1	40mm Thick on floors to even finish. <u>Finish with Polyscreed MD (colour of choice) at a nominal thickness of 4 mm as per manufacturer's instructions to falls and allow to cure for a minimum of 24 hours. Cut and seal joints with Solid joint LV100</u> <u>Install 75mm high covings using Solidcove Mortar and Sealing with Polyscreed Lockcoat to match the floor.</u>	m2	48	
2	Concrete floors	m2	48	
	<u>INTERNAL PLASTER</u>			
	<u>Cement plaster on brickwork</u>			
3	On superstructure internal walls	m2	60	
	Carried Forward to Summary of Section No. 5		R	
	Section No. 5 Bill No. 5 Plastering Mavusandile Solutions (PTY) LTD			

[illegible]

Item No	Quantity	Rate	Amount
<u>SECTION NO.5</u>			
<u>BILL NO. 7</u>			
<u>PLUMBING AND DRAINAGE</u>			
<u>(PROVISIONAL)</u>			
<u>Preambles</u>			
TheTenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2008 Edition)			
<u>WORK GROUP 146</u>			
<u>RAINWATER DISPOSAL</u>			
<u>Seamless Aluminium Gutters and Downpipes</u>			
1	125 x 75 x 0,6mm aluminium ogee gutter with baked enamel finish fixed with concealed brackets.	m	17
2	Extra over 250mm girth eaves box gutter for stopped end	No	4
3	Extra over 250mm girth box eaves gutter for outlet for 100 x 75mm pipe	No	2
4	100 x 75 x 0,6mm Fluted aluminium downpipes with white baked enamel finish.	m	10
5	Extra over 100 x 75mm diameter rainwater pipe for bend	No	8
6	Extra over 100 x 75mm rainwater pipe for shoe	No	2
7	Extra over 100 x 75mm rainwater pipe for eaves or plinth offset 600mm projection	No	2
<u>WORK GROUP 148</u>			
<u>SANITARY FITTINGS</u>			
Carried Forward			R
Section No. 5 Bill No. 7 Plumbing & Drainage Mavusandile Solutions (PTY) LTD			

**ERADICATION OF PIT LATRINES
ENZONDWANE PRIMARY SCHOOL**

Brought Forward			R
<u>"Atlas Plastics" or similar approved plastic sanitary fittings including connection to services and fixing to walls or floors.</u>			
<u>Water Closet, basins, urinals,etc</u>			
8	223 AP, VIP 200 toilet pedestal for VIP toilets complete with lid and single flap heavy duty plastic seat fitted as per manufacturer's instructions.	No	10
9	496AP Waterless urinal fitting and waste	No	
10	382AP Christy wash hand basin including brackets,etc.	No	4
<u>"Cobra"</u>			
<u>TRAPS ETC</u>			
<u>"Marley"</u>			
11	38mm Deep seal "P" or "S" trap	No	4
<u>WASTE UNIONS ETC</u>			
12	32mm Basin waste union	No	4
<u>TAPS, VALVES, ETC</u>			
<u>"Cobra Watertech"</u>			
13	15mm Chrome plated ball-o-stop valve	No	3
14	Star pillar tap (Code 111-20)	No	4
15	Cobra Water tech 15mm chrome plated elbow action raised nose pillar tap with blue indicator for cold water (Code: 503-21B), manufactured in accordance with SANS 226:2004 Type 2 (BS 5412).	No	1
<u>Brass</u>			
16	22mm Stopcock	No	2
17	28mm Fullway gate valve	No	2
Carried Forward			R
Section No. 5 Bill No. 7 Plumbing & Drainage Mavusandile Solutions (PTY) LTD			

**ERADICATION OF PIT LATRINES
ENZONDWANE PRIMARY SCHOOL**

Brought Forward			R
<u>SANITARY PLUMBING</u>			
<u>uPVC pipes in walls, cast in slabs etc.</u>			
18	50mm Pipes	m	37
19	110mm Pipes	m	25
<u>200mm HD Vent Pipe with Windmaster Extractor</u>			
20	200mm diameter, 2.5mm HDPVC vent pipe attached to RoofWhirllys4Africa Toilet	m	14
<u>Extra over uPVC pipes for fittings</u>			
21	50mm Fittings	No	20
22	110mm Fittings.	No	10
23	200mm Fittings.	No	5
<u>WATER SUPPLIES</u>			
<u>Polycop pipes</u>			
24	15mm Polycop pipe to walls,etc	m	27
25	22mm Polycop pipe to walls,etc	m	18
26	15mm Polycop pipe in ground < 1m deep	m	13
27	22mm Polycop pipe in ground < 1m deep	m	25
<u>Extra over Class 2 copper pipes for brass compression fittings</u>			
28	15mm Fittings	No	21
29	22mm Fittings	No	27
Carried Forward			R
Section No. 5 Bill No. 7 Plumbing & Drainage Mavusandile Solutions (PTY) LTD			

ERADICATION OF PIT LATRINES ENZONDWANE PRIMARY SCHOOL

[illegible]

Item No		Quantity	Rate	Amount
	<u>SECTION NO.5</u>			
	<u>BILL NO. 8</u>			
	<u>GLAZING</u>			
	<u>Preambles</u>			
	TheTenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2008 Edition)			
	<u>SUPPLEMENTARY PREAMBLES</u>			
	<u>Note: Glazing of laminated safety glass into steel frames: all edges to be sealed with 15mm selotape to prevent water absorption via the vinyl interlayer. Glass to be set on 25mm neoprene rubber setting blocks of 60 - 90 degree sure hardness</u>			
	<u>WORK GROUP 150</u>			
	<u>GLAZING TO STEEL WITH PUTTY</u>			
	<u>6.38mm Arctic Snow safety laminated glass</u>			
1	Panes exceeding 0,1m2 and not exceeding 0.5m2	m2	3	
	<u>MIRRORS ETC</u>			
	<u>6mm Silvered float glass copper backed mirrors with polished edges holed for and fixed with chromium plated dome capped mirror screws with rubber buffers to plugs in brickwork or concrete.</u>			
2	600 x 600mm high mirror	No	4	
	Carried Forward to Summary of Section No. 5		R	
	Section No. 5			
	Bill No. 8			
	Glazing			
	Mavusandile Solutions (PTY) LTD			

Item No	Quantity	Rate	Amount
<u>SECTION NO.5</u>			
<u>BILL NO. 9</u>			
<u>PAINTWORK</u>			
<u>Preambles</u>			
TheTenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2008 Edition)			
<u>SUPPLEMENTARY PREAMBLES</u>			
<u>PREPARATORY WORK TO EXISTING WORK</u>			
<u>Previously painted plastered surfaces</u>			
Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks shall be opened, filled with a suitable filler and finished smooth			
<u>Previously painted metal surfaces</u>			
Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal			
<u>Previously painted wood surfaces</u>			
Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth			
<u>WORK GROUP 152</u>			
<u>PAINTWORK ETC TO NEW WORK</u>			
<u>FLOATED PLASTER SURFACES WITH</u>			
Carried Forward			R
Section No. 5 Bill No. 9 Paintwork Mavusandile Solutions (PTY) LTD			

Brought Forward			R
<u>One coat Dulux trade alkali resistant plaster primer, apply one Dulux Trade universal undercoat and two coats full strength, dulux pearlglo solvent based enamel (or similar approved)</u>			
1	Internal walls	m2	60
<u>ON FASCIAS AND BARGE BOARDS</u>			
<u>Prepare and apply one coat Dulux primer, one coat Dulux undercoat for all surfaces and two coats Dulux weatherguard ultrasmooth</u>			
2	On fascias and barge boards	m2	8
<u>ON METAL</u>			
<u>Prepare and apply Dulux cleaner to galvanised iron, One coat Dulux primer for galvanised iron, one coat Dulux universal undercoat and two coats Dulux gloss enamel to galvanised steel</u>			
3	Security gates and screens	m2	11
4	Windows	m2	6
<u>ON WOOD</u>			
<u>Prepare and apply one coat Dulux primer for wood, one coat Dulux trade universal undercoat and two coats Dulux trade pearlglo paint</u>			
5	On doors & frames	m2	28
<u>PAINTS TO ROOF TRUSSES, PURLINS, BRANDERING, WALLS PLATES ETC.</u>			
6	Prepare and brush surface to remove all loose contaminants and apply Four coats "ABE Provonite" or equal approved carbolineum anti-corrosive coal tar paint on All Trusses	m2	28
Carried Forward to Summary of Section No. 5			R
Section No. 5			
Bill No. 9			
Paintwork			
Mavusandile Solutions (PTY) LTD			

ERADICATION OF PIT LATRINES
ENZONDWANE PRIMARY SCHOOL

SECTION SUMMARY - BOYS - 10B, 4WHB		Page No	Amount	
Bill No				
1	Roof Coverings	70		
2	Carpentry & Joinery	73		
3	Ironmongery	75		
4	Metalwork	76		
5	Plastering	77		
6	Tiling	78		
7	Plumbing & Drainage	82		
8	Glazing	83		
9	Paintwork	85		
Carried to Final Summary			R	
Section No. 5				
Mavusandile Solutions (PTY) LTD				

Item No		Quantity	Rate	Amount
	<u>SECTION NO.6</u>			
	<u>BILL NO 1</u>			
	<u>EXTERNAL WORKS, ETC.</u>			
	<u>Preambles</u>			
	TheTenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2008 Edition)			
	<u>WORK GROUP 104 (EARTHWORKS)</u>			
	<u>SITE CLEARANCE, ETC.</u>			
	<u>Removal of surface vegetable matter</u>			
1	Allow for digging up, carting and depositing all grass, rubbish, debris, building rubble, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc to existing pond on site.	m2	280	
	<u>Removal of Topsoil</u>			
2	Excavate average 150mm deep to remove topsoil and deposit on site in spoil heap for future use .	m2	280	
	<u>CONCRETE WALKWAYS</u>			
	<u>Earthworks</u>			
3	Excavate in earth to reduce levels not exceeding 2 m deep.	m3	39	
4	Extra over all excavations for carting surplus excavated material from the site.	m3	20	
5	Scarify ground to a depth of 150 mm and re-compact to 90% Mod. AASHTO density.	m2	130	
	Carried Forward		R	
	Section No. 6 Bill No. 1 SITE WORKS(PROVISIONAL) Mavusandile Solutions (PTY) LTD			

	Brought Forward			R
6	Approved G7 natural crushed stone as base course 150 mm thick compacted to 98% Modified AASHTO density under pavings	m3	59	
	<u>Concrete Paving Blocks</u>			
	<u>Paving of 50mm thick 200x100mm 25MPa Bevel Bond paver blocks grey in colour in herringbone pattern on and including 20mm thick sand bed with dry filler sand swept and vibrated into joints all laid on subgrade (elsewhere measured) conforming to SABS 1200D degree of accuracy I:</u>			
7	Paving to walkway areas, etc laid to falls.	m2	130	
8	Extra over ordinary paving for 200mm wide block-on-flat header course edging on 100mm thick mortar bed including unreinforced concrete haunching along outside edge.	m	240	
	<u>Kerbing</u>			
	<u>Precast or in situ mass concrete (25 MPa - 19 mm stone) kerbs cast in convenient lengths with exposed faces finished smooth from the mould and all salient angles rounded, jointed and pointed in 1:3 cement mortar, including excavations, formwork, etc.</u>			
9	Figure 8B (300 x 275 x 175mm) semi mountable kerb laid in lengths not exceeding 1000mm on a well rammed earth bottom or base course.	m	240	
	<u>OPEN STORMWATER CHANNELS</u>			
	<u>WORK GROUP 104 (EARTHWORKS)</u>			
	<u>Excavation not exceeding 2m deep</u>			
10	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	18	
	<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>			
11	Off site to a dumping site to be found by the Contractor.	m3	18	
	Carried Forward			R
	Section No. 6 Bill No. 1 SITE WORKS(PROVISIONAL) Mavusandile Solutions (PTY) LTD			

**ERADICATION OF PIT LATRINES
ENZONDWANE PRIMARY SCHOOL**

Brought Forward			R
	<u>Filling supplied by the contractor under channels</u>		
12	G7 Base course material compacted to 98% Mod AASHTO density	m3	18
13	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	18
	<u>Cast in-situ Ref 395 mesh reinforced concrete (25MPa) open stormwater channels having V-shaped waterway formed in top, finished smooth on all exposed surfaces in 3:1 cement plaster trowelled smooth and with angles rounded, cast in suitable lengths not exceeding 2m, including all formwork, moulds, shallow excavation, filling and ramming, laying to falls, bedding and pointing in 3:1 cement mortar. Concrete apron to be tinted, colour to be specified by the Engineer.</u>		
14	700 x 80mm thick V' channel 150mm deep in centre laid in position in ground in 2000mm sections including all formwork, reinforcement, expansion joints, smooth finishing to top of concrete surface etc.	m	100
15	Extra for 700mm angle	No	16
16	Extra for forming 200mm thick 700mm wide spreader with 200mm high edges fanning out to 1 960mm width at furthest end with hard burnt bricks pitching cast in ass diffusers including working off concrete to a smooth finish and draining onto natural ground with 150 - 200mm diameter loose stones.	No	4
	<u>WORK GROUP 146 (DRAINAGE)</u>		
	<u>Reno Mattresses of 2,7mm diameter PVC coated galvanised wire boxes laced together and filled with broken stone</u>		
17	300mm Thick Reno mattress formed of 3500 x 1000mm boxes properly bonded in accordance with the manufacturers instructions, the last 300mm to be buried into insitu ground.	No	4
	<u>CONCRETE APRONS</u>		
Carried Forward			R
Section No. 6 Bill No. 1 SITE WORKS(PROVISIONAL) Mavusandile Solutions (PTY) LTD			

**ERADICATION OF PIT LATRINES
ENZONDWANE PRIMARY SCHOOL**

Brought Forward			R
<u>WORK GROUP 104 (EARTHWORKS)</u>			
<u>Earthworks</u>			
18	Excavate in earth to reduce levels not exceeding 2 m deep.	m3	21
19	Extra over all excavations for carting surplus excavated material from the site.	m3	21
20	Scarify ground to a depth of 150 mm and re-compact to 90% Mod. AASHTO density.	m2	78
21	Approved G5 natural crushed stone as base course 150 mm thick compacted to 98% Modified AASHTO density under pavings	m3	12
22	Termite and ant proofing of ground surfaces under pavings, etc.	m2	65
<u>WORK GROUP 110 (CONCRETE)</u>			
<u>Concrete</u>			
23	Cement concrete 25 MPa/20mm stone in surface bed	m3	7
<u>WORK GROUP 111 (FORMWORK)</u>			
<u>Formwork</u>			
24	Formwork to edges, risers, ends and reveals not exceeding 300mm high or wide	m	86
25	Extra for floating off smooth tops of aprons to falls with a wood float.	m2	65
<u>10mm Thick Jointex or other approved compressible joint filler</u>			
26	10mm Joints not exceeding 300mm high	m	86
<u>WORK GROUP 114 (REINFORCEMENT)</u>			
Carried Forward			R
Section No. 6 Bill No. 1 SITE WORKS(PROVISIONAL) Mavusandile Solutions (PTY) LTD			

**ERADICATION OF PIT LATRINES
ENZONDWANE PRIMARY SCHOOL**

Brought Forward			R
<u>Reinforcement</u>			
27	Reference 193 welded mesh reinforcement lapped 300mm at edge of adjoining sheets and bound with annealed wire and laying in concrete surface beds (Measured nett - no allowance made for laps)	m2	65
<u>WORK GROUP 120(WATERPROOFING)</u>			
<u>Waterproofing</u>			
<u>Approved polysulphide sealing compound including backing cord, bond breaker, primer etc.:</u>			
28	10mm Wide x 10mm deep in vertical expansion joints between concrete and concrete or brick surfaces, including raking out expansion joint filler as necessary	m	86
<u>THE FOLLOWING IN ACCESS DRIVEWAY, ETC.</u>			
<u>Excavation not exceeding 2m deep</u>			
29	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	35
<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>			
30	Off site to a dumping site to be found by the Contractor.	m3	35
<u>Filling supplied by the contractor under driveways</u>			
31	G7 Base course material compacted to 98% Mod AASHTO density	m3	4
32	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	4
<u>Rip and Re - compact insitu material on site compacted to 93% Mod. AASHTO density:</u>			
33	Under floors,etc.	m2	55
Carried Forward			R
Section No. 6 Bill No. 1 SITE WORKS(PROVISIONAL) Mavusandile Solutions (PTY) LTD			

ERADICATION OF PIT LATRINES ENZONDWANE PRIMARY SCHOOL

Brought Forward			R
	<u>Prescribed density tests on filling:</u>		
34	In-situ dry density test.	No	5
	<u>Approved brand of anti-termite soil poison applied by a Registered Pest Control Company and guaranteed against termite infestation for ten years:</u>		
35	Treat filling under paving with 'Chlordane Heptachlor Aldrin' or equal approved.	m2	55
Carried to Final Summary			R
Section No. 6			
Bill No. 1			
SITE WORKS(PROVISIONAL)			
Mavusandile Solutions (PTY) LTD			

[illegible]

Item No	Quantity	Rate	Amount
<u>SECTION NO.8</u>			
<u>BILL NO 1</u>			
<u>PROVISIONAL SUMS ETC</u>			
<u>Preambles</u>			
TheTenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2008 Edition)			
<u>SUPPLEMENTARY PREAMBLES</u>			
<u>Work executed by direct contractors</u>			
Work listed under the heading "DIRECT CONTRACTORS WORK" will commence during the excecution of this contract and the contractor shall allow free access to the site for these direct contractors. The contractor shall prepare a programme in conjunctionwith these direct contractors in order to complete the work successfully. The direct contractors will be regarded as nominated sub-contractors but payment will not be made to them via the contractor. The estimated values of these contracts are listedto enable the contractor to determine profit and attendances, if required			
<u>General</u>			
Unless otherwise described, all prime cost amounts and provisional sums exclude the cash discount of 5% and include for delivery to site of all articles concerned			
All prime cost amounts and provisional sums are net and include for delivery to siteof all articles concerned			
<u>Preliminaries</u>			
The contractor is referred to the Preliminaries for further amplification of "Prime Cost Amounts and Provisional Sums"			
Carried Forward		R	
Section No. 8 Bill No. 1 PROVISIONAL AMOUNTS Mavusandile Solutions (PTY) LTD			

Brought Forward

BUDGETARY ALLOWANCES

The following budgetary allowance are for work to be executed at rates in the bills of quantities or to be agreed bby the Principal agent:

WORK GROUP 190

TEMPORARY ABLUTIONS

- | | |
|---|--|
| 1 | Provide the amount of R120 000.00 (One Hundred and Eighty Thousand Rand) for temporary ablutions, to be executed complete. |
|---|--|

ELECTRICAL INSTALLATION & LIGHTNING PROTECTION.

- | | |
|---|---|
| 2 | Allow a provisional sum of R 140 000 (One Hundred And Forty Thousand Rands) for electrical installation and lightning protection by a specialist sub-contractor. |
| 3 | Allow for profit and Attendance on the above item. |

R

Item

120 000,00

Item

140 000,00

%

Carried to Final Summary

R

Section No. 8

Bill No. 1

PROVISIONAL AMOUNTS

Mavusandile Solutions (PTY) LTD

ERADICATION OF PIT LATRINES ENZONDWANE PRIMARY SCHOOL

[illegible]